

Preliminary

01/14/2022 1:13:56 PM

PART V

City of Bend Standard Drawings

Part V – City of Bend Standard Drawings

Table of Contents

ROADWAY **R**

Typical Street Cross-Sections – General Notes.....	R-1
Typical Street Cross-Sections – Arterial	R-1A
Typical Street Cross-Sections – Major Collector.....	R-1B
Typical Street Cross-Sections – Minor Collector.....	R-1C
Typical Street Cross-Sections – Local	R-1D
Typical Street Cross-Sections – Industrial Local.....	R-1E
Typical Street Section – Alley	R-1F
Typical Street Dead-End Turnaround	R-1G
Clear Vision Areas at Intersections.....	R-2
Concrete Curb.....	R-3
Concrete Curb Notes.....	R-3A
Shared-Use Path/Sidewalk, Setback.....	R-4A
Shared-Use Path/Sidewalk, Curb-Tight	R-4B
Driveway Approach, Setback (Standard).....	R-5A
Driveway Approach, Setback, Partially Lowered (Alternate B).....	R-5B
Driveway Approach, Curb-Tight, Fully Lowered (Alternate C).....	R-5C
Driveway Approach, Curb-Tight, Partially Lowered (Alternate D).....	R-5D
Driveway Approach, Curb-Tight, Wrapping Sidewalk (Alternate E).....	R-5E
Curb Ramp General Notes	R-6
Typical Perpendicular Curb Ramp.....	R-6A
Typical Parallel Curb Ramp.....	R-6B
Curb Ramp Details.....	R-6C
PSST Anchor Base Foundation.....	R-7
PSST Slip Base Foundation	R-7A
Removal Post and Markings.....	R-7B
Standard Street Name Signs.....	R-8
Standard Street Sign Placement	R-9
Typical Trench Section.....	R-10
Franchise Utility Joint Trench	R-10A
Trench Surface Restoration.....	R-11

Patterned Colored Concrete Detail.....	R-24
Median End Detail.....	R-25
Local Street Curb Extensions.....	R-26
Collector / Local Intersection.....	R-27
Accessible Parking – Angle.....	R-29
Speed Humps and Sharrow Placement.....	R-32
Raised Crosswalk.....	R-33
Traffic Circle.....	R-34
Rectangular Rapid Flashing Beacon.....	R-35
Pavement Markings – White.....	R-40
Pavement Markings – Yellow.....	R-41
Pavement Markings.....	R-42A
Pavement Markings.....	R-42B
Pavement Markings - Bike.....	R-43
Pavement Markings - Bike.....	R-43A
Turn Lane Marking Layout.....	R-44
Intersection Bike Safety.....	R-44A
Bike Lane Markings.....	R-44B
Bike Lane Markings.....	R-44C
Intersection Pavement Marking Layout.....	R-45
Crosswalk Markings.....	R-47
Primary Trail.....	R-48
Connector Trail.....	R-49

SANITARY

S

Sewer Main Typical Profile.....	S-1
Gravity Sewer/Storm Services on New Mains.....	S-2A
Gravity Sewer/Storm Service Connection to Existing Main.....	S-2B
Gravity Sewer/Storm Cleanout.....	S-2C
Standard Sewer Manhole Ring & Cover.....	S-3A
Composite Manhole Frame and Cover.....	S-3B
Standard Sewer/Storm Manhole.....	S-3C
Typical Manhole Invert Layout.....	S-3D
Standard Outside Drop - Larger Than 12" Pipe.....	S-4
Standard Inside Drop – 12" Pipe and Smaller.....	S-4A
3" & 4" Pressure Sewer Line Termination Cleanout.....	S-5

Air Release/Vac Breaker Pressure Sewer MH.....	S-6
Main Line Cleanout Pressure Sewer	S-7
Pressure Sewer Service – Traffic Area.....	S-8
Pressure Sewer Service – Non Traffic Area	S-9
Industrial and Commercial Services Sampling MH	S-15
Vacuum Sewer Service	S-16

WATER

W

Water Main Typical Profile.....	W-1
Residential Water Service Installation	W-4
3/4"-1" Residential Meter Service Installation	W-4A
3/4"-1" Residential Meter Service Installation	W-4B
Commercial & IRR Meter Service Installation.....	W-5
1" Commercial & IRR Meter Service Installation.....	W-5A
1 1/2" & 2" Commercial and Irrigation Meter Service Installation	W-5B
3" & 4" Commercial Meter Installation	W-5C
6" and Larger Commercial Meter Installation	W-5D
Meter Installation in Sidewalks	W-5E
Galv. Ladder w/ Alum Ext For Water Vaults	W-6
Typical Hydrant	W-7
Hydrant Location and Clear Zone.....	W-8
Separation of Water Line to Irrigation Culverts	W-9
1" & 2" Standard Air Release Valve – Traffic Area.....	W-10
1" Standard Air Release Valve	W-10A
2" Standard Air Release Valve	W-10B
Typical DCVA Installations 2" and Smaller	W-13
2" & Larger Double Check Valve Assembly.....	W-13A
Fire Sprinkler Line	W-13B
2 1/2"-10" Reduced Pressure Backflow Assembly.....	W-15
1"-2" Reduced Pressure Backflow Assembly.....	W-15A
2 1/2" + Reduced Pressure Backflow Assembly	W-15B
Fire Gate	W-21
Hydrant Permit/Filling Tanker Truck	W-22
Standard 2" Blow-Off Assembly.....	W-23
4" Blow-Off Detail	W-24
Standard Water Sampling Station	W-25

Cross Connection Detail.....	W-29
Valve Box and Operator Extension Assembly	W-30

STORMWATER

STRM

Vegetated Swale Detail	STRM-2
Typical Swale Layout	STRM-3
Typical Curb Cut	STRM-3A
Check Dam Detail	STRM-4
Stormwater Planter Detail	STRM-5
Stormwater Filter Detail	STRM-6
Stormwater Sedimentation Manhole.....	STRM-7
Stormwater Sedimentation Manhole – Alternate.....	STRM-7A
Stormwater Manhole Lid Detail	STRM-8
Standard Catch Basin Special Inlets	STRM-9
Standard Pre-Cast Drywell	STRM-10
Drywell w/ Manufactured Treatment Layout	STRM-11
Standard Catch Basin	STRM-12
Stormwater Grate.....	STRM-13A
Combination Catch Basin Inlet	STRM-13B
Existing Catch Basin Pavement Resurfacing.....	STRM-14
Infiltration Pond Detail	STRM-16
Chainlink Fence Detail	STRM-17
Curb Weep Hole Detail.....	STRM-18

EROSION CONTROL

E

Sediment Fence Detail	E-1
Bio-Filter Bag Inlet Protection	E-2A
Filter Insert Inlet Protection.....	E-2B
Tree/Vegetation Protection Fencing	E-3
Straw Wattle.....	E-4
Slope / Stockpile Stabilization	E-5
Erosion Blanket – Channel Installation	E-6
Concrete Truck Washout.....	E-7
Gravel Construction Entrance	E-8

LANDSCAPING

L

Planting or Turf Bed Drip Layout	L-1
Sprinkler Head and Joint	L-2
Irrigation Sleeve Under Paving	L-3
Irrigation – Typical Trench	L-4
Irrigation Fittings.....	L-5
Irrigation Remote Control Valve	L-6
Irrigation Blow Out.....	L-7
Termination Point	L-8
Quick Coupling Valve	L-9
Drip Control Valve, Filter, and Regulator	L-10
1” Comm. Control Zone Kit with Basket Filter	L-12
Air Relief Valve in Kit – AR Valve Kit	L-13
Drip Irrigation Mainline Layout.....	L-14
Point Source Drip Emitter	L-15
Dripline 2” Below Grade Potable System.....	L-16
Landscape Dripline Flush Point Potable System	L-17
Tree Root Watering System Detail	L-18
Tree Well Detail.....	L-19

Preliminary

01/14/2022 1:13:59 PM

CITY OF BEND STANDARD DRAWINGS

Roadway (R)

GENERAL NOTES FOR STD DWGS R-1A THROUGH R-1F:


1. CENTER STREETS IN THE RIGHT-OF-WAY UNLESS OTHERWISE APPROVED BY CITY ENGINEER FOR UNIQUE TRANSITIONS OR SITE CONSTRAINTS.
2. THE LEVEL OF TRAFFIC STRESS PER THE ODOT APM CH. 14 IS SHOWN ON EACH STANDARD CROSS-SECTION. ANY MODIFICATION OF THE CROSS-SECTIONS MUST PROVIDE THE APPROPRIATE LTS.
3. INSTALL SIDEWALKS/SHARED-USE PATHS PROPERTY TIGHT. SIDEWALKS/SHARED-USE PATHS MAY MEANDER AROUND UTILITIES, TREES, AND OTHER NON-MOVEABLE OBJECTS. EASEMENTS ARE REQUIRED WHERE SIDEWALK/SHARED-USE PATH MEANDERS OUT OF THE RIGHT-OF-WAY.
4. PAVEMENT SECTIONS FOR STREETS AND SIDEWALKS PER THE THICKNESSES NOTED IN TABLE BELOW OR AS SPECIFIED IN A STAMPED GEOTECHNICAL REPORT APPROVED BY THE CITY ENGINEER.
5. RETAINING WALLS AND STAIRS ARE NOT PERMITTED WITHIN THE RIGHT-OF-WAY UNLESS OTHERWISE APPROVED BY THE CITY ENGINEER.
6. STREET CROSS-SECTION/IMPROVEMENT STANDARDS ARE BASED ON STREET CLASSIFICATION. REFERENCE THE BEND DEVELOPMENT CODE SECTION 3.4 PUBLIC IMPROVEMENTS STANDARDS AND STANDARD CROSS-SECTIONS FOR ADDITIONAL DETAIL.
7. THE CROSS-SLOPE OF THE PLANTER STRIP BETWEEN THE CURB AND RIGHT-OF-WAY SHALL NOT BE STEEPER THAN 4H:1V TO PROVIDE A RECOVERABLE ROADSIDE SLOPE. 50H:1V (2%) IS TYPICAL/PREFERRED.
8. MAX 1.5H:1V CUT SLOPES PERMITTED IN ROCK CUTS WHEN APPROVED BY A GEOTECHNICAL ENGINEER.
9. MASTER PLAN DEVELOPMENTS PER BEND DEVELOPMENT CODE 4.5.100(E)(2)(C) MAY PROPOSE MODIFIED STREET SECTIONS THAT INCLUDE ADDITIONS TO OR ENHANCEMENTS OF THE BASIC MINIMUM STANDARD SECTIONS SHOWN HERE. ANY ALTERNATE SECTIONS MUST PROVIDE FOR THE MINIMUM ELEMENT WIDTHS SHOWN IN THE CROSS-SECTIONS.
10. OFF STREET SHARED-USE PATHS (PATHS MEETING THE GENERAL ALIGNMENT OF THE TSP LOW STRESS NETWORK AND ARE MORE THAN 30 FT OUTSIDE OF THE RIGHT-OF-WAY) ARE ENCOURAGED, PARTICULARLY ALONG ARTERIAL STREET CORRIDORS. SIDEWALKS MAY BE REDUCED TO A MINIMUM 6 FT OR ELIMINATED WHEN THE SAME SIDE OF THE ROAD CORRIDOR IS SERVED BY A SHARED-USE PATH DEPENDING ON ADJACENT LAND USE AND PEDESTRIAN/BIKE ACCESS AND WITH CITY ENGINEER APPROVAL.
11. TWELVE-FOOT CENTER MEDIAN ON ARTERIAL AND COLLECTOR CROSS-SECTIONS INCLUDES EITHER A STRIPED MEDIAN (TWO-WAY LEFT TURN LANE, DOUBLE YELLOW, AND/OR TURN BAY) OR A NINE-FOOT RAISED REFUGE ISLAND WITH A ONE AND A HALF FOOT SHY LINE STRIPE EACH SIDE AS REQUIRED PER STANDARDS.
12. RAISED MEDIANS ARE AT THE CITY ENGINEER'S DISCRETION ON ARTERIALS & COLLECTORS. MEDIAN REFUGE ISLANDS FOR STREET CROSSINGS ON A LOW STRESS ROUTE OR AN ENHANCED CROSSING ON A CONNECTOR ROUTE DO NOT REQUIRE CITY ENGINEER APPROVAL.
13. ON-STREET PARKING SPACES ARE NOT STRIPED. IN HIGH PARKING DEMAND AREAS, A PARKING LINE MAY BE USED WITH CITY ENGINEER APPROVAL.
14. SEE BEND DEVELOPMENT CODE 3.4.200(F)(3) FOR STREETS AND INTERSECTIONS NOT IDENTIFIED FOR TRAVEL LANE EXPANSION WHERE ADDITIONAL RIGHT-OF-WAY IS NOT REQUIRED FOR VEHICLE TRAVEL LANES.
15. PLTS = PEDESTRIAN LEVEL OF TRAFFIC STRESS / BLTS = BICYCLISTS LEVEL OF TRAFFIC STRESS.
16. DEVIATIONS FROM THE PAVEMENT SECTIONS PROVIDED IN THE TABLE BELOW REQUIRE A STAMPED GEOTECHNICAL REPORT. PCC ROADWAYS REQUIRE A STAMPED GEOTECHNICAL REPORT.
17. SEE CITY SPEC 00744/00745 FOR MAXIMUM AC PAVEMENT LIFT THICKNESS.
18. WHERE EXISTING GROUND CROSS SLOPE EXCEEDS 12%, CURB-TIGHT SIDEWALK IS ALLOWED PER DESIGN STANDARD 3.4.7 - HILLSIDE.

STREET TYPE	"A" ROW	"B" STREET	"C" SIDEWALK	"D" CURB	"E" ACP DEPTH/LEVEL	"F" BASE	"G" CUT/FILL
ARTERIAL	PER R-1A			7"/16"	8" - LEVEL IV	10"	4H:1V
COLLECTOR	PER R-1B & R-1C			6"/14"	6" - LEVEL III	8"	4H:1V
LOCAL	PER R-1D			6"/12"	4" - LEVEL III	6"	2H:1V
INDUSTRIAL LOCAL	PER R-1D			6"/12"	4" - LEVEL III	8"	2H:1V
ALLEY	PER R-1E			--	4" - LEVEL III	6"	2H:1V
ROUNDAABOUT - ACP	VARIES	VARIES	VARIES	**	8" - LEVEL IV	10"	4H:1V
ROUNDAABOUT - PCC ***	VARIES	VARIES	VARIES	**	*	*	4H:1V


* THE STANDARD PAVEMENT SECTION FOR ARTERIAL STREETS IS ASPHALT. FOR RECONSTRUCTION, NEW STREETS MORE THAN 1/4 MILE LONG, AND FOR ROUNDAABOUTS, A LIFE CYCLE COST ANALYSIS EVALUATING ASPHALT, PERPETUAL PAVEMENT, CONCRETE, AND OTHER SECTIONS SHALL BE SUBMITTED TO AND APPROVED BY THE CITY ENGINEER.

* CURBS AT ROUNDAABOUTS AND ON SPLITTER ISLANDS SHALL BE HIGH-STRENGTH PER CITY SPEC 00759.13.

*** DOWELING REQUIRED AT ROUNDAABOUT JOINTS

DRAWN AJD	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV ROADWAY			DATE 12/10/21
REV			DATE
		TYPICAL STREET CROSS-SECTIONS - GENERAL NOTES	APPR
			STD DWG R-1

01/14/2022 1:14:00 PM



PLTS: 1 ≤ 35 MPH
2 ≥ 40 MPH

BLTS: 1
(SUP)

BLTS: 1 ≤ 30 MPH
(BIKE LANE) 2 = 35 MPH
3 ≥ 40 MPH

ARTERIAL GENERAL NOTES:

- SEE R-1 FOR GENERAL NOTES.
- WHERE PERMITTED BY THE BEND DEVELOPMENT CODE, ON-STREET PARKING MAY BE PROVIDED ON ARTERIAL STREETS WITH SPEEDS 35 MPH OR LESS. ON-STREET PARKING DESIGN PER ENGINEERING STANDARDS.
- PROTECTED BIKE LANES, OTHER THAN PARKING PROTECTED, REQUIRE CITY ENGINEER APPROVAL. PARKING PROTECTED BIKE LANES ALLOWED ON A CASE-BY-CASE BASIS.
- SIDEWALK MAY MEANDER WITH A MINIMUM 5 FT PLANTER STRIP. DESIGN MEANDERING CURVES FOR 10 MPH.
- FOR EXISTING ARTERIAL SECTIONS IN 100 FT RIGHT-OF-WAY WITH 52 FT PAVEMENT WIDTHS, THE CITY ENGINEER MAY APPROVE REDUCING THE BIKE LANE TO 6/2.5 FT TO MATCH THE 52 FT CURB-TO-CURB EXISTING CONSTRUCTED SECTIONS; EXCEPTION DOES NOT APPLY TO SECTIONS (NEW OR RECONSTRUCTED) AT THE OUTER EXTENTS OF THE NETWORK WHERE UNDEVELOPED LAND AND FUTURE EXPANSIONS/RECONSTRUCTIONS CAN ACCOMMODATE THE 56/72 FT PAVEMENT SECTION.
- THE FIVE-LANE ARTERIAL SECTION IS TO BE USED ON 3RD STREET, 27TH STREET SOUTH OF NEFF ROAD, REED MARKET ROAD EAST OF US 97, AND OTHER MAJOR ARTERIAL STREETS AS IDENTIFIED BY A TRAFFIC ANALYSIS WITH CITY ENGINEER APPROVAL (SEE STANDARDS FOR LANE ADDITIONS).
- PARKING IS NOT PERMITTED ON A FIVE LANE ARTERIAL.
- FOR PARKING ON ONE SIDE OF A THREE LANE ARTERIAL, COMBINE THE APPLICABLE HALF STREET SECTIONS FROM THE NO PARKING AND PARKING ON BOTH SIDES TYPICAL SECTIONS. THE ROAD CENTERLINE SHALL REMAIN IN THE CENTER OF ROW TO ALLOW FOR FUTURE EXPANSION.

DRAWN A.J.D.
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL STREET CROSS-SECTIONS - ARTERIAL


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-1A

01/14/2022 1:14:00 PM



PLTS: 1 ≤ 35 MPH
2 ≥ 40 MPH

BLTS: 1
(SUP)

BLTS: 1 ≤ 30 MPH
(BIKE LANE) 2 = 35 MPH
3 ≥ 40 MPH

MAJOR COLLECTOR GENERAL NOTES:

- SEE R-1 FOR GENERAL NOTES.
- WHERE PERMITTED BY THE BEND DEVELOPMENT CODE, ON-STREET PARKING MAY BE PROVIDED ON COLLECTOR STREETS WITH SPEEDS 35 MPH OR LESS. ON-STREET PARKING DESIGN PER ENGINEERING STANDARDS.
- WHERE THE CROSS-SECTION DOES NOT PROVIDE FOR TREES IN A PLANTER STRIP, DEVELOPMENT MUST STILL MEET BEND DEVELOPMENT CODE TREE REQUIREMENTS IN AN ALTERNATE LOCATION ON-SITE OR PROVIDE MITIGATION AND RECEIVE APPROVAL OF A VARIANCE AS REQUIRED BY CODE.
- PROTECTED BIKE LANES, OTHER THAN PARKING PROTECTED, REQUIRE CITY ENGINEER APPROVAL. PARKING PROTECTED BIKE LANES ALLOWED ON A CASE-BY-CASE BASIS.
- SIDEWALK MAY MEANDER WITH A MINIMUM 5 FT PLANTER STRIP. DESIGN MEANDERING CURVES FOR 10 MPH.
- PARKING PROTECTED BIKE LANES ALLOWED ON A CASE-BY-CASE BASIS.
- FOR PARKING ON ONE SIDE, COMBINE THE APPLICABLE HALF STREET SECTIONS FROM THE NO PARKING AND PARKING ON BOTH SIDES TYPICAL SECTIONS. THE ROAD CENTERLINE SHALL REMAIN IN THE CENTER OF ROW TO ALLOW FOR FUTURE EXPANSION.

DRAWN A.J.D.
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SCALE NTS


DATE 12/10/21

APPR

STD DWG R-1B

TYPICAL STREET CROSS-SECTIONS - MAJOR COLLECTOR

01/14/2022 1:14:00 PM



PLTS: 1 ≤ 35 MPH
2 ≥ 40 MPH

BLTS: 1
(SUP)

BLTS: 1 ≤ 30 MPH
(BIKE LANE) 2 = 35 MPH
3 ≥ 40 MPH

MINOR COLLECTOR GENERAL NOTES:

- SEE R-1 FOR GENERAL NOTES.
- WHERE PERMITTED BY THE BEND DEVELOPMENT CODE, ON-STREET PARKING MAY BE PROVIDED ON COLLECTOR STREETS WITH SPEEDS 35 MPH OR LESS. ON-STREET PARKING DESIGN PER ENGINEERING STANDARDS.
- WHERE THE CROSS-SECTION DOES NOT PROVIDE FOR TREES IN A PLANTER STRIP, DEVELOPMENT MUST STILL MEET BEND DEVELOPMENT CODE TREE REQUIREMENTS IN AN ALTERNATE LOCATION ON-SITE OR PROVIDE MITIGATION AND RECEIVE APPROVAL OF A VARIANCE AS REQUIRED BY CODE.
- PROTECTED BIKE LANES, OTHER THAN PARKING PROTECTED, REQUIRE CITY ENGINEER APPROVAL. PARKING PROTECTED BIKE LANES ALLOWED ON A CASE-BY-CASE BASIS.
- SIDEWALK MAY MEANDER WITH A MINIMUM 5 FT PLANTER STRIP. DESIGN MEANDERING CURVES FOR 10 MPH.
- PARKING ON SIDE ALLOWED BY DROPPING PARKING FROM OTHER SIDE IN BOTTOM SECTION - KEEP ROAD CL IN ROW CENTER.
- FOR PARKING ON ONE SIDE, COMBINE THE APPLICABLE HALF STREET SECTIONS FROM THE NO PARKING AND PARKING ON BOTH SIDES TYPICAL SECTIONS. THE ROAD CENTERLINE SHALL REMAIN IN THE CENTER OF ROW TO ALLOW FOR FUTURE EXPANSION.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SCALE NTS


DATE 12/10/21

APPR

STD DWG R-1C

TYPICAL STREET CROSS-SECTIONS - MINOR COLLECTOR

01/14/2022 1:14:00 PM



DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND
STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL STREET CROSS-SECTION - LOCAL


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-1D

01/14/2022 1:14:00 PM



INDUSTRIAL LOCAL - PARKING BOTH SIDES

PLTS:1 BLTS:1
2 (STRIPED CENTERLINE)

LOCAL ROAD GENERAL NOTES:

- SEE R-1 FOR GENERAL NOTES
- THE SIDE PARKING IS ON MAY ALTERNATE BY BLOCK. PROVIDE PARKING NEXT TO PARKS, SCHOOLS, AND OTHER ACTIVITY GENERATING LAND USES.
- UTILITY EASEMENTS MAY BE REQUIRED FOR PEDESTALS, TRANSFORMERS, ETC.
- FOR PARKING ON ONE SIDE, COMBINE THE APPLICABLE HALF STREET SECTIONS FROM THE NO PARKING AND PARKING ON BOTH SIDES TYPICAL SECTIONS. THE ROAD CENTERLINE SHALL REMAIN IN THE CENTER OF ROW TO ALLOW FOR FUTURE EXPANSION.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


TYPICAL STREET CROSS-SECTION - INDUSTRIAL LOCAL

SCALE NTS

DATE 12/10/21


APPR

STD DWG R-1E



ALTERNATIVE ALLEY

ASPHALT BASE AND WEARING COURSES.
THICKNESS PER "E" IN TABLE ON STD
DWG R-1 AND PER CITY SPEC 00744



STANDARD ALLEY

AGGREGATE BASE PER "F" IN
TABLE ON STD DWG R-1 AND
PER CITY SPEC 00640

ALLEY GENERAL NOTES:

- SEE R-1 FOR GENERAL NOTES.
- NEW ALLEY RIGHT-OF-WAY AND PAVED WIDTH WILL BE 20' WIDE. WHERE ALLEYS ARE INSTALLED IN EXISTING RIGHT-OF-WAY, THE PAVED WIDTH MAY BE UP TO 2 FEET LESS THAN THE RIGHT-OF-WAY WIDTH. 1-FOOT WIDE BUFFERS ON EACH SIDE OF THE ALLEY MAY BE LEFT UNPAVED WHEN ALLEYS ARE INSTALLED IN EXISTING RIGHT-OF-WAY.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL STREET SECTION - ALLEY

SCALE NTS


DATE 12/10/21

APPR

STD DWG R-1F

Preliminary

01/14/2022 1:14:00 PM



CUL-DE-SAC GENERAL NOTES:

1. SEE R-1 FOR GENERAL NOTES.
2. SEE STD DWG R-1 AND R-1D FOR PAVEMENT AND BASE AGGREGATE DEPTHS ON LOCAL ROADS

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL STREET DEAD-END TURNAROUND


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-1G


01/14/2022 1:14:00 PM











CLEAR VISION AREAS ARE ESTABLISHED AS FOLLOWS:

- 1) CLEAR VISION TRIANGLES SHALL BE ESTABLISHED AT THE CORNER OF ANY PROPERTY ADJACENT TO INTERSECTIONS OF PUBLIC OR PRIVATE STREETS, ALLEYS, MID-BLOCK LANES, AND/OR RAILROAD RIGHTS-OF-WAY.
- 2) THE TWO LEGS OF THE CLEAR VISION TRIANGLE ARE EACH MEASURED FROM THE POINT OF INTERSECTION OF THE TWO CORNER LOT LINES, SPECIAL SETBACK LINES, OR ACCESS EASEMENT LINES. WHERE LOT LINES HAVE ROUNDED CORNERS, THE LOT LINES ARE EXTENDED IN A STRAIGHT LINE TO A POINT OF INTERSECTION. THE CLEAR VISION AREA EXTENDS TO THE FACE OF CURB AT THE STREET OR ALLEY
- 3) THE LENGTH OF BOTH LEGS OF THE CLEAR VISION AREA TRIANGLE IS AS FOLLOWS:
 TYPICAL, ALL ZONES: 15 FEET
 RAILROADS: 15 FEET
 ALLEY INTERSECTION: 10 FEET
 DRIVEWAYS: 10 FEET
- 4) WITHIN THE CLEAR VISION AREA, OBSTRUCTIONS TO VISION OTHER THAN A STREET SIGN, POST, OR POLE LESS THAN 8 INCHES IN DIAMETER SHALL BE CLEARED FROM PROPERTY UNDER THE CONTROL OF THE CITY, HOMEOWNER, OR DEVELOPER. SHRUBS OR FOLIAGE MUST NOT EXCEED 2'-0" IN HEIGHT. PLANTING NEW TREES OR INSTALLATION OF COMMUNICATION TOWERS AND TRANSFORMERS, ARE NOT PERMITTED WITHIN THE CLEAR VISION AREA. EXISTING TREES MUST BE MAINTAINED/LIMBED TO A MINIMUM OF 8'-0" ABOVE THE TOP OF CURB OR 12'-0" ABOVE ADJACENT BIKE LANES.
- 5) DRIVEWAY APPROACHES AND DRIVEWAYS ARE NOT PERMITTED WITHIN THE CLEAR VISION AREA. ON-STREET PARKING DESIGN DOES NOT INCLUDE SPACES WITHIN 20 FEET OF AN ACCESSIBLE RAMP OR WITHIN 10 FEET OF A DRIVEWAY APPROACH.


NOTE: INTERSECTION SIGHT TRIANGLES ARE DISTINCT FROM, AND IN ADDITION TO, CLEAR VISION AREAS. INTERSECTION SIGHT TRIANGLE DIMENSIONS VARY WITH STREET WIDTH, GEOMETRY, TOPOGRAPHY, AND POSTED SPEED; ADDITIONAL CLEARING AS NECESSARY TO PROVIDE CLEAR INTERSECTION SIGHT DISTANCE IS ALSO REQUIRED; SEE CHAPTER 3.3 OF THE CITY OF BEND DESIGN STANDARDS.

DRAWN AJD	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV ROADWAY			DATE 12/10/21
REV DATE			APPR
		CLEAR VISION AREAS AT INTERSECTIONS	STD DWG R-2

01/14/2022 11:44:00 AM



ROAD CLASS	CURB HEIGHT - H	CURB EXPOSURE - E	GUTTER WIDTH - G
ARTERIAL	16"	7"	12"
COLLECTOR	14"	6"	18"
LOCAL	12"	6"	18"



SEE NOTES ON STD DWG R-3A

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND
STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

CONCRETE CURB

SCALE NTS

DATE 12/10/21


APPR

STD DWG R-3


01/14/2022 1:14:00 PM

NOTES FOR STD DWG R-3.


1. EXPANSION JOINTS REQUIRED AT END OF RADII, DRIVEWAY APRONS, POINTS OF CURVATURE, AND NO GREATER THAN 150' MAXIMUM.
2. AGGREGATE BASE SHALL CONFORM TO SPECIFICATION SECTION 00640/00641. DEPTH AS REQUIRED TO MATCH BOTTOM OF STREET SECTION, 4" MIN.
3. SLOPE DRIVEWAY TOWARD STREET. 3/4" MAXIMUM LIP AT GUTTER, 1" ON COLLECTORS AND ARTERIALS.
4. MOUNTABLE CURB PERMITTED ON LOCAL STREET CUL-DE-SACS, ALLEYS, AND WHERE PERMITTED BY THE CITY ENGINEER. WHERE SIDEWALK ABUTS CURB, SIDEWALK SHALL BE MIN. 6" THICK
5. CURB AND GUTTER MAY BE REQUIRED WHEN GUTTER SLOPE IS BETWEEN 0.5% - 0.75%.
6. WEEP HOLE CURBS ON RESIDENTIAL STREETS ONLY WHERE APPROVED. SIDEWALK CANNOT BE PLACED CURB TIGHT WITH WEEP HOLES. SEE R-4A AND STRM-18.
7. CONCRETE MATERIAL AND PLACEMENT SHALL CONFORM TO SPECIFICATION SECTION 00759.
8. LOCATE TAPERED CURB ON DOWNSTREAM SIDE OF PEDESTRIAN REFUGE IN CENTER MEDIAN CURB RAMPS TO PROTECT FROM SNOW PLOW DAMAGE.

DRAWN AJD	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS	
DIV ROADWAY			DATE 12/10/21	
REV		DATE	CONCRETE CURB NOTES	APPR
				STD DWG R-3A

01/14/2022 1:14:00 PM



TYPICAL CROSS SECTION



GENERAL NOTES FOR ALL DETAILS:

1. SIDEWALKS SET BACK ADJACENT TO PROPERTY LINE ARE STANDARD. USE CURB-TIGHT SIDEWALKS ONLY WHERE PERMITTED. SIDEWALK SHALL BE PROPERTY-TIGHT EXCEPT TO MEANDER AROUND TREES OR BARRIERS (UTILITIES, SIGNS, ETC.) OR PER DESIGN STANDARD SECTION 3.4.7 - HILLSIDE.
2. CONST. EXPANSION JOINTS AT 25' MAXIMUM SPACING, AND AT POINTS OF TANGENCY, AND ON EACH SIDE OF DRIVEWAY APRONS. EXPANSION JOINTS MUST BE FULL DEPTH OF PAVING SECTION.
3. CONST. CONTRACTION JOINTS AT 5' MAXIMUM SPACING, AND AT ENDS OF EACH RAMP.
4. FOR DRIVEWAY DETAILS, SEE STD. DRGS. R-5A THROUGH R-5E.
5. SIDEWALK THICKNESS MINIMUM 4" THICK, TYPICAL. MINIMUM 6" THICK IF SIDEWALK IS INTENDED AS PORTION OF DRIVEWAY, CURB RAMP, OR ADJACENT TO MOUNTABLE CURB.
6. ASPHALT SHARED-USE PATH WHERE APPROVED BY THE ENGINEER.

DRAWN A.J.D.
DIV. ROADWAY
REV. DATE



CITY OF BEND

CITY OF BEND
STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SHARED-USE PATH/SIDEWALK, SETBACK



SCALE NTS

DATE 12/10/21

APPR


STD DWG R-4A

01/14/2022 1:14:00 PM




* PROVIDE COMPACTED BACKFILL
ADJACENT TO CURB AND SIDEWALK

TYPICAL CROSS SECTION



TYPICAL PLAN VIEW



★ WHEN SITE CONSTRAINTS PROHIBIT A 5' PASSAGE, THE ENGINEER MAY DIRECT THIS TO BE REDUCED, BUT NO LESS THAN 4'.

REQUIRED SIDEWALK WIDENING
AROUND OBSTRUCTIONS

GENERAL NOTES FOR ALL DETAILS:

1. SIDEWALKS SET BACK ADJACENT TO PROPERTY LINE ARE STANDARD. USE CURB-TIGHT SIDEWALKS ONLY WHERE PERMITTED.
2. CONST. EXPANSION JOINTS AT 25' MAXIMUM SPACING, AND AT POINTS OF TANGENCY, AND ON EACH SIDE OF DRIVEWAY APRONS. EXPANSION JOINTS MUST BE FULL DEPTH OF PAVING SECTION.
3. CONST. CONTRACTION JOINTS AT 5' MAXIMUM SPACING, AND AT ENDS OF EACH RAMP.
4. FOR DRIVEWAY DETAILS, SEE STD. DRGS. R-5A THROUGH R-5E.
5. SIDEWALK THICKNESS MINIMUM 4" THICK, TYPICAL. MINIMUM 6" THICK IF SIDEWALK IS PORTION OF DRIVEWAY, CURB RAMP, OR ADJACENT TO MOUNTABLE CURB.
6. ASPHALT SHARED-USE PATH WHERE APPROVED BY THE ENGINEER.

DRAWN A.J.D.
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


SHARED-USED PATH/SIDEWALK, CURB-TIGHT

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-4B




**TYPICAL PLAN AND PROFILE VIEW
DRIVEWAY APPROACH, SETBACK SIDEWALK (STANDARD)**

TABLE 1 - APPROACH WIDTH (W)	
TYPE	WIDTH
RESIDENTIAL	10' - 24'
SINGLE FAMILY	10'-24'
TOWNHOME	32' MAX SHARED ; 16' MAX LOCAL STREETS
DUPLEX	SUM 32' MAX (2 APRON MAX)
TRIPLEX	SUM 32' MAX (3 APRON MAX)
MULTIFAMILY	20' - 30'
COMMERCIAL	10' - 35'

TABLE 2 - DRIVEWAY APPROACH WITH SETBACK SIDEWALK SPECIFICATIONS				
TYPE OF STREET	SIDEWALK WIDTH	LIP EXPOSURE	APRON GRADE, POSITIVE GRADE TO ROW	FLARE WIDTH
LOCAL	PER R-1D	$\frac{3}{4}$ "	12.0% MAX	3'
COLLECTOR	PER R-1B & R-1C	1"	12.0% MAX	6'
ARTERIAL	PER R-1A	1"	12.0% MAX	6'

GENERAL NOTES:

- SIDEWALKS SHALL MEET ALL STANDARDS OF CURRENT PUBLIC RIGHTS OF WAY ACCESSIBILITY GUIDELINES (PROWAG).
- CURB AND SIDEWALK TYPES VARY, SEE PLANS. SEE STD. DRG. R-3 FOR CURB DETAILS. SEE STD. DRGS. R-4A & R-4B FOR SIDEWALK DETAILS.
- TOOLED JOINTS ARE REQUIRED AT ALL DRIVEWAY SLOPE BREAK LINES.
- THE LANDING SHALL BE PAVED WITH CONCRETE OR ASPHALT SURFACE FOR A MINIMUM OF 20 FEET. PAVING BEYOND THE LANDING SHALL BE IN ACCORDANCE WITH THE BEND DEVELOPMENT CODE. CONSTRUCT AS DIRECTED OR AS SHOWN ON PLANS. DO NOT ENTER PRIVATE PROPERTY WITHOUT APPROPRIATE PERMIT OR EASEMENT. MATERIAL WITHIN THE ROW SHALL BE CONCRETE.
- CHECK THE GUTTER FLOW DEPTH AT DRIVEWAY LOCATIONS TO ASSURE THAT THE DESIGN FLOOD DOES NOT OVERTOP THE BACK OF SIDEWALK AT DRIVEWAY. IF OVERTOPPING OCCURS PLACE AN INLET AT UPSTREAM SIDE OF DRIVEWAY OR PERFORM OTHER APPROVED DESIGN MITIGATION.
- #4 REBAR (2"0" ON CENTER, TO BE SUSPENDED TO CENTER OF CONCRETE DEPTH) REQUIRED IN COMMERCIAL AND INDUSTRIAL DRIVEWAYS AND IN PUBLIC ALLEYS. 6"x6" 10 GAUGE MINIMUM WELDED WIRE MAY BE USED IN LIEU OF REBAR.
- CONCRETE DRIVEWAY APRON REQUIRED WHERE SIDEWALK AND/OR CURB IS EXISTING/PROPOSED, OTHERWISE AN ASPHALT APPROACH CAN BE INSTALLED TO EDGE OF PAVEMENT TO SIMILAR WIDTHS OF THE DRIVEWAY APRON AS APPROVED BY THE CITY ENGINEER.
- REFER TO THE BEND DEVELOPMENT CODE 3.1.400 AND 3.6.200 FOR NUMBER AND WIDTH OF APRONS PERMITTED PER LOT.
- THIS SAME STANDARD APPLIES TO ALLEYS

DRAWN AJD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV ROADWAY			DATE 12/10/21
REV DATE			APPR
			STD DWG R-5A
DRIVEWAY APPROACH, SETBACK (STANDARD)			

ACCESSIBLE PATH TO BE CONSTRUCTED ON BACK SIDE OF APRONS REGARDLESS OF PRESENCE OF SIDEWALK




TABLE 1 - APPROACH WIDTH (W)

TYPE	WIDTH
RESIDENTIAL	10' - 24'
SINGLE FAMILY	10'-24'
TOWNHOME	32' MAX SHARED ; 16' MAX LOCAL STREETS
DUPLEX	SUM 32' MAX (2 APRON MAX)
TRIPLEX	SUM 32' MAX (3 APRON MAX)
MULTIFAMILY	20' - 30'
COMMERCIAL	10' - 35'

TYPICAL PLAN AND PROFILE VIEW
DRIVEWAY APPROACH, SETBACK, PARTIALLY LOWERED
(ALTERNATE B)

TABLE 2 - DRIVEWAY APPROACH WITH SETBACK SIDEWALK SPECIFICATIONS

TYPE OF STREET	SIDEWALK WIDTH	LIP EXPOSURE	APRON GRADE, POSITIVE GRADE TO ROW	FLARE WIDTH
LOCAL	PER R-1D	$\frac{3}{4}$ "	12.0% MAX	3'
COLLECTOR	PER R-1B & R1-C	1"	12.0% MAX	6'
ARTERIAL	PER R-1A	1"	12.0% MAX	6'

GENERAL NOTES:

- SIDEWALKS SHALL MEET ALL STANDARDS OF CURRENT PUBLIC RIGHTS OF WAY ACCESSIBILITY GUIDELINES (PROWAG).
- CURB AND SIDEWALK TYPES VARY, SEE PLANS. SEE STD. DRG. R-3 FOR CURB DETAILS. SEE STD. DRGS. R-4A & R-4B FOR SIDEWALK DETAILS.
- TOOLED JOINTS ARE REQUIRED AT ALL DRIVEWAY SLOPE BREAK LINES.
- THE LANDING SHALL BE PAVED WITH CONCRETE OR ASPHALT SURFACE FOR A MINIMUM OF 20 FEET. PAVING BEYOND THE LANDING SHALL BE IN ACCORDANCE WITH THE BEND DEVELOPMENT CODE. CONSTRUCT AS DIRECTED OR AS SHOWN ON PLANS. DO NOT ENTER PRIVATE PROPERTY WITHOUT APPROPRIATE PERMIT OR EASEMENT. MATERIAL WITHIN THE ROW SHALL BE CONCRETE.
- CHECK THE GUTTER FLOW DEPTH AT DRIVEWAY LOCATIONS TO ASSURE THAT THE DESIGN FLOOD DOES NOT OVERTOP THE BACK OF SIDEWALK AT DRIVEWAY. IF OVERTOPPING OCCURS PLACE AN INLET AT UPSTREAM SIDE OF DRIVEWAY OR PERFORM OTHER APPROVED DESIGN MITIGATION.
- #4 REBAR (2"0" ON CENTER, TO BE SUSPENDED TO CENTER OF CONCRETE DEPTH) REQUIRED IN COMMERCIAL AND INDUSTRIAL DRIVEWAYS AND IN PUBLIC ALLEYS. 6"x6" 10 GAUGE MINIMUM WELDED WIRE MAY BE USED IN LIEU OF REBAR.
- CONCRETE DRIVEWAY APRON REQUIRED WHERE SIDEWALK AND/OR CURB IS EXISTING/PROPOSED, OTHERWISE AN ASPHALT APPROACH CAN BE INSTALLED TO EDGE OF PAVEMENT TO SIMILAR WIDTHS OF THE DRIVEWAY APRON AS APPROVED BY THE CITY ENGINEER.
- REFER TO THE BEND DEVELOPMENT CODE 3.1.400 AND 3.6.200 FOR NUMBER AND WIDTH OF APRONS PERMITTED PER LOT.
- THIS SAME STANDARD APPLIES TO ALLEYS

DRAWN A.JD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND
STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


DRIVEWAY APPROACH, SETBACK, PARTIALLY LOWERED (ALTERNATE B)

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-5B




**TYPICAL PLAN AND PROFILE VIEW
DRIVEWAY APPROACH, CURB-TIGHT, PARTIALLY LOWERED (ALTERNATE D)**

TABLE 1 - APPROACH WIDTH (W)	
TYPE	WIDTH
RESIDENTIAL	10' - 24'
SINGLE FAMILY	10'-24'
TOWNHOME	32' MAX SHARED ; 16' MAX LOCAL STREETS
DUPLEX	SUM 32' MAX (2 APRON MAX)
TRIPLEX	SUM 32' MAX (3 APRON MAX)
MULTIFAMILY	20' - 30'
COMMERCIAL	10' - 35'

TABLE 2 - DRIVEWAY APPROACH WITH SETBACK SIDEWALK SPECIFICATIONS				
TYPE OF STREET	SIDEWALK WIDTH	LIP EXPOSURE	APRON GRADE, POSITIVE GRADE TO ROW	FLARE WIDTH
LOCAL	PER R-1D	$\frac{3}{4}$ "	12.0% MAX	3'
COLLECTOR	PER R-1B & R-1-C	1"	12.0% MAX	6'
ARTERIAL	PER R-1A	1"	12.0% MAX	6'

GENERAL NOTES:



- SIDEWALKS SHALL MEET ALL STANDARDS OF CURRENT PUBLIC RIGHTS OF WAY ACCESSIBILITY GUIDELINES (PROWAG).
- CURB AND SIDEWALK TYPES VARY, SEE PLANS. SEE STD. DRG. R-3 FOR CURB DETAILS. SEE STD. DRGS. R-4A & R-4B FOR SIDEWALK DETAILS.
- TOOLED JOINTS ARE REQUIRED AT ALL DRIVEWAY SLOPE BREAK LINES.
- THE LANDING SHALL BE PAVED WITH CONCRETE OR ASPHALT SURFACE FOR A MINIMUM OF 20 FEET. PAVING BEYOND THE LANDING SHALL BE IN ACCORDANCE WITH THE BEND DEVELOPMENT CODE. CONSTRUCT AS DIRECTED OR AS SHOWN ON PLANS. DO NOT ENTER PRIVATE PROPERTY WITHOUT APPROPRIATE PERMIT OR EASEMENT. MATERIAL WITHIN THE ROW SHALL BE CONCRETE.
- CHECK THE GUTTER FLOW DEPTH AT DRIVEWAY LOCATIONS TO ASSURE THAT THE DESIGN FLOOD DOES NOT OVERTOP THE BACK OF SIDEWALK AT DRIVEWAY. IF OVERTOPPING OCCURS PLACE AN INLET AT UPSTREAM SIDE OF DRIVEWAY OR PERFORM OTHER APPROVED DESIGN MITIGATION.
- #4 REBAR (2" ON CENTER, TO BE SUSPENDED TO CENTER OF CONCRETE DEPTH) REQUIRED IN COMMERCIAL AND INDUSTRIAL DRIVEWAYS AND IN PUBLIC ALLEYS. 6"x6" 10 GAUGE MINIMUM WELDED WIRE MAY BE USED IN LIEU OF REBAR.
- CONCRETE DRIVEWAY APRON REQUIRED WHERE SIDEWALK AND/OR CURB IS EXISTING/PROPOSED, OTHERWISE AN ASPHALT APPROACH CAN BE INSTALLED TO EDGE OF PAVEMENT TO SIMILAR WIDTHS OF THE DRIVEWAY APRON AS APPROVED BY THE CITY ENGINEER.
- REFER TO THE BEND DEVELOPMENT CODE 3.1.400 AND 3.6.200 FOR NUMBER AND WIDTH OF APRONS PERMITTED PER LOT.
- THIS SAME STANDARD APPLIES TO ALLEYS

DRAWN AJD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV ROADWAY			DATE 12/10/21
REV DATE			APPR
			STD DWG R-5D

CITY OF BEND

DRIVEWAY APPROACH, CURB-TIGHT, PARTIALLY LOWERED (ALTERNATE D)

ACCESSIBLE PATH TO BE CONSTRUCTED ON BACK SIDE OF APRONS REGARDLESS OF PRESENCE OF SIDEWALK



**TYPICAL PLAN VIEW
DRIVEWAY APPROACH, CURB-TIGHT, WRAPPING SIDEWALK
(ALTERNATE E)**

TABLE 1 - APPROACH WIDTH (W)	
TYPE	WIDTH
RESIDENTIAL	10' - 24'
SINGLE FAMILY	10'-24'
TOWNHOME	32' MAX SHARED ; 16' MAX LOCAL STREETS
DUPLEX	SUM 32' MAX (2 APRON MAX)
TRIPLEX	SUM 32' MAX (3 APRON MAX)
MULTIFAMILY	20' - 30'
COMMERCIAL	10' - 35'

TABLE 2 - DRIVEWAY APPROACH SPECIFICATIONS WITH CURB-TIGHT WRAPPING SIDEWALK				
TYPE OF STREET	MINIMUM SIDEWALK WIDTH	LIP EXPOSURE	APRON GRADE, POSITIVE GRADE TO ROW	FLARE WIDTH
LOCAL	PER R-1D	$\frac{3}{4}$ "	12.0% MAX	3'
COLLECTOR	PER R-1B & R1-C	1"	12.5% MAX	6'
ARTERIAL	PER R-1A	1"	12.5% MAX	6'

GENERAL NOTES:

- SIDEWALKS SHALL MEET ALL STANDARDS OF CURRENT PUBLIC RIGHTS OF WAY ACCESSIBILITY GUIDELINES (PROWAG).
- CURB AND SIDEWALK TYPES VARY, SEE PLANS. SEE STD. DRG. R-3 FOR CURB DETAILS. SEE STD. DRGS. R-4A & R-4B FOR SIDEWALK DETAILS.
- TOOLED JOINTS ARE REQUIRED AT ALL DRIVEWAY SLOPE BREAK LINES.
- THE LANDING SHALL BE PAVED WITH CONCRETE OR ASPHALT SURFACE FOR A MINIMUM OF 20 FEET. PAVING BEYOND THE LANDING SHALL BE IN ACCORDANCE WITH THE BEND DEVELOPMENT CODE. CONSTRUCT AS DIRECTED OR AS SHOWN ON PLANS. DO NOT ENTER PRIVATE PROPERTY WITHOUT APPROPRIATE PERMIT OR EASEMENT. MATERIAL WITHIN THE ROW SHALL BE CONCRETE.
- CHECK THE GUTTER FLOW DEPTH AT DRIVEWAY LOCATIONS TO ASSURE THAT THE DESIGN FLOOD DOES NOT OVERTOP THE BACK OF SIDEWALK AT DRIVEWAY. IF OVERTOPPING OCCURS PLACE AN INLET AT UPSTREAM SIDE OF DRIVEWAY OR PERFORM OTHER APPROVED DESIGN MITIGATION.
- #4 REBAR (2"0" ON CENTER, TO BE SUSPENDED TO CENTER OF CONCRETE DEPTH) REQUIRED IN COMMERCIAL AND INDUSTRIAL DRIVEWAYS AND IN PUBLIC ALLEYS. 6"x6" 10 GAUGE MINIMUM WELDED WIRE MAY BE USED IN LIEU OF REBAR.
- CONCRETE DRIVEWAY APRON REQUIRED WHERE SIDEWALK AND/OR CURB IS EXISTING/PROPOSED, OTHERWISE AN ASPHALT APPROACH CAN BE INSTALLED TO EDGE OF PAVEMENT TO SIMILAR WIDTHS OF THE DRIVEWAY APRON AS APPROVED BY THE CITY ENGINEER.
- REFER TO THE BEND DEVELOPMENT CODE 3.1.400 AND 3.6.200 FOR NUMBER AND WIDTH OF APRONS PERMITTED PER LOT.
- THIS SAME STANDARD APPLIES TO ALLEYS

DRAWN A.JD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

DRIVEWAY APPROACH, CURB-TIGHT, WRAPPING SIDEWALK (ALTERNATE E)

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-5E

GENERAL NOTES :

1. CITY OF BEND STD DWGS R-6, R-6A, R-6B, AND R-6C ARE INTENDED AS A SUMMARY OF PROWAG REQUIREMENTS. SEE CURRENT PROWAG GUIDELINES FOR COMPLETE REQUIREMENTS.
2. SLOPES USED FOR DESIGN ARE TYPICALLY LESS THAN THE MAXIMUMS TO ALLOW FOR CONSTRUCTION TOLERANCES. RECOMMENDED DESIGN SLOPES ARE AS FOLLOWS:

PROWAG MAX. SLOPE	DESIGN MAX. SLOPE
1:10 (10%)	9.5%
1:12 (8.33%)	7.5%
1:20 (5.0%)	4.5%
1:50 (2%)	1.5%

3. GRADE BREAKS ARE NOT PERMITTED ON THE SURFACE OF CURB RAMPS, BLENDED TRANSITIONS, LANDINGS, AND GUTTER AREAS WITHIN THE PEDESTRIAN ACCESS ROUTE.
4. THE COUNTER SLOPE OF THE GUTTER OR STREET AT THE FOOT OF A CURB RAMP, LANDING, OR BLENDED TRANSITION SHALL BE 5% MAXIMUM.
5. SURFACES OF CURB RAMPS, BLENDED TRANSITIONS, AND LANDINGS SHALL COMPLY WITH R302.7. GRATINGS, ACCESS COVERS, AND OTHER APPURTENANCES SHALL NOT BE LOCATED ON CURB RAMPS, LANDINGS, BLENDED TRANSITIONS AND GUTTERS WITHIN THE PEDESTRIAN ACCESS ROUTE.
6. SURFACE DISCONTINUITIES SHALL NOT EXCEED 0.5 in. MAXIMUM. VERTICAL DISCONTINUITIES BETWEEN 0.25 in. AND 0.5 in. MAXIMUM SHALL BE BEVELED AT 1:2 MINIMUM. THE BEVEL SHALL BE APPLIED ACROSS THE ENTIRE LEVEL CHANGE. SEE PROWAG R302.7.2.
7. WHERE SIDEWALKS ARE CONSTRUCTED OUTSIDE THE RIGHT OF WAY, A PUBLIC ACCESS EASEMENT MUST BE RECORDED OVER THE PRIVATE PROPERTY ENCROACHMENT.
8. 6 INCHES OF COMMERCIAL GRADE CONCRETE PER CITY SPEC 00440 AND 4 INCHES OF STATE SPEC AGGREGATE PER CITY SPEC 00640/00641 IS REQUIRED FOR CONSTRUCTION OF CURB RAMPS, FLARES, AND LANDINGS.
9. DETECTABLE WARNING SURFACES COMPLYING WITH PROWAG R305 SHALL BE PROVIDED, WHERE A CURB RAMP, LANDING, OR BLENDED TRANSITION CONNECTS TO A STREET.
10. DETECTABLE WARNING SURFACES SHALL EXTEND 24 in. MINIMUM IN THE DIRECTION OF TRAVEL AND THE FULL WIDTH OF THE CURB RAMP (EXCLUSIVE OF FLARES), THE LANDING, OR THE BLENDED TRANSITION.
11. THE ROWS OF TRUNCATED DOMES IN A DETECTABLE WARNING SURFACE SHALL BE ALIGNED TO BE PERPENDICULAR OR RADIAL TO THE GRADE BREAK BETWEEN THE RAMP, LANDING, OR BLENDED TRANSITION AND THE STREET.
12. THE CLEAR WIDTH OF LANDINGS BLENDED TRANSITIONS, AND CURB RAMPS, EXCLUDING FLARES, SHALL BE 4.0 FT. MINIMUM.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

CURB RAMP GENERAL NOTES

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-6

10:01 PM

CURB EXPOSURE TO BE MINIMUM 3-INCHES (6-INCH PREFERRED) BETWEEN RAMPS UNLESS OTHERWISE APPROVED.

GRADE BREAKS AT THE TOP AND BOTTOM OF PERPENDICULAR CURB RAMPS SHALL BE PERPENDICULAR TO THE DIRECTION OF RAMP RUN. AT LEAST ONE END OF THE BOTTOM GRADE BREAK SHALL BE AT THE BACK OF CURB. THE GRADE FROM THE BOTTOM OF THE DETECTABLE WARNING TO THE LANDING SHALL BE A CONTINUOUS GRADE (5% MAXIMUM). SURFACE SLOPES THAT MEET THE GRADE BREAKS SHALL BE FLUSH.

FLARED SIDES ARE PREFERRED, PARTICULARLY WHERE SUBJECT TO DAMAGE FROM ONCOMING TRAFFIC AND SNOWPLOWS. IF ADJACENT CONSTRAINTS PREVENT FLARE CONSTRUCTION, SIDE OF RAMPS MAY BE RETURNED IF PROTECTED FROM CROSS TRAVEL BY LANDSCAPING, STREET FURNITURE, POLES, OR EQUIPMENT.

ONE CORNER OF THE DETECTABLE WARNING MUST BE WITHIN 2 in. OF THE GRADE BREAK; NO OTHER POINT ON THE LEADING EDGE OF THE DETECTABLE WARNING MAY BE MORE THAN 5 ft. FROM THE BACK OF CURB.

WHERE BOTH ENDS OF THE BOTTOM GRADE BREAK, COMPLYING WITH PROWAG R305.2.1, ARE 5.0 ft. OR LESS FROM THE BACK OF CURB, THE DETECTABLE WARNING SHALL BE LOCATED ON THE RAMP SURFACE AT THE BOTTOM GRADE BREAK. WHERE EITHER END OF THE BOTTOM GRADE BREAK IS MORE THAN 5.0 ft. FROM THE BACK OF CURB, THE DETECTABLE WARNING SHALL BE LOCATED ON THE LOWER LANDING.

FLARED SIDES WITH A SLOPE OF 10% MAXIMUM, MEASURED PARALLEL TO THE CURB LINE, SHALL BE PROVIDED WHERE A PEDESTRIAN CIRCULATION PATH CROSSES THE CURB RAMP OR WHEN THE FLARE ABUTS A HARD SURFACE.

FLARES REQUIRED UNLESS BARRIERS EXIST OR WHERE APPROVED BY THE CITY ENGINEER. FLARE SLOPE CAN EXCEED 10% WHERE ABUTTING MIN 2' LANDSCAPING AREA.

A LANDING 5.0 ft. MINIMUM BY 5.0 ft. MINIMUM SHALL BE PROVIDED AT THE TOP OF THE CURB RAMP AND SHALL BE PERMITTED TO OVERLAP OTHER LANDINGS AND CLEAR SPACE. RUNNING AND CROSS SLOPES AT INTERSECTIONS SHALL BE 2% MAXIMUM.

PERPENDICULAR CURB RAMPS











THE RUNNING SLOPE SHALL BE 5% MINIMUM AND 8.3% MAXIMUM BUT SHALL NOT REQUIRE THE RAMP LENGTH TO EXCEED 15.0 FT.

BLENDED TRANSITIONS SHALL COMPLY WITH R303.3. RUNNING SLOPE SHALL BE 5% MAXIMUM AND CROSS SLOPE SHALL BE 2% MAXIMUM.

THE RAMP CROSS SLOPE SHALL NOT EXCEED 2% AT YIELD OR STOP CONTROLLED INTERSECTIONS. AT UNCONTROLLED INTERSECTIONS, THE CROSS SLOPE MAY TRANSITION FROM 2% AT THE LANDING UP TO 5% AT THE CURB. AT MIDBLOCK CROSSINGS, THE CROSS SLOPE MAY TRANSITION TO MATCH THE ROAD GRADE.

WIDTH OF RAMP TO MATCH SUP/SIDEWALK STANDARD WIDTH FOR ROAD CROSS-SECTION; ALTERNATE MAY BE APPROVED BY CITY ENGINEER IN EXISTING NON-COMPLIANT AREAS WITH NO PLANS FOR SIDEWALK UPGRADES.

TRANSITION PANEL FROM RAMP TO EXISTING SIDEWALK (WHERE REQUIRED TO MATCH EX. SIDEWALK CROSS SLOPE). MAX. GRADES ARE NOT SPECIFIED BY PROWAG. ADJUST LENGTH AS NEEDED TO PROVIDE 0.5% CHANGE PER FT. IF PROPOSED MATCH LINE LOCATION FALLS WITHIN 2 FEET FROM AN EXISTING JOINT IN THE SECTION OF SIDEWALK TO REMAIN, THE EXISTING WALK SHALL BE REMOVED BACK TO THE NEXT JOINT.

-  SIDEWALK OR OTHER TRAVERSABLE SURFACE
-  DETECTABLE WARNING SURFACE (DWS)
-  LEVEL AREA (TURNING SPACE/LANDING) 2% MAX. SLOPE IN ANY DIRECTION
-  CROSS SLOPE 2.0% MAX.
-  RUNNING SLOPE 5.0% MAX.
-  RUNNING SLOPE 8.3% MAX.
-  COUNTER SLOPE 5.0% MAX. ASCENDING OR DESCENDING
-  FLARE SLOPE 10% MAX.
-  4'X4' CLEAR SPACE
-  REQUIRED DESIGN ELEVATIONS SLOPES TO BE SHOWN WITH DESIGN

TYPICAL PERPENDICULAR CURB RAMP
ACCORDING TO PROWAG REQUIREMENTS
NOT TO SCALE - ROTATED TO FIT

DRAWN A.J.D.
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL PERPENDICULAR CURB RAMP

SCALE NTS

DATE 12/10/21


APPR

STD DWG R-6A

01/14/2022 1:14:01 PM

TRANSITION PANEL FROM RAMP TO EXISTING SIDEWALK (WHERE REQUIRED TO MATCH EX. SIDEWALK CROSS SLOPE). MAX. GRADES ARE NOT SPECIFIED BY PROWAG. ADJUST LENGTH AS NEEDED TO PROVIDE SMOOTH TRANSITION. IF PROPOSED MATCH LINE LOCATION FALLS WITHIN 2 FEET FROM AN EXISTING JOINT IN THE SECTION OF SIDEWALK TO REMAIN, THE EXISTING WALK SHALL BE REMOVED BACK TO THE NEXT JOINT.

GRADE BREAKS AT THE TOP AND BOTTOM OF PARALLEL CURB RAMP SHALL BE PERPENDICULAR TO THE DIRECTION OF RAMP RUN. SURFACE SLOPES THAT MEET THE GRADE BREAKS SHALL BE FLUSH.



PARALLEL CURB RAMP

THE RUNNING SLOPE SHALL BE 8.33% MAXIMUM BUT SHALL NOT REQUIRE THE RAMP LENGTH TO EXCEED 15.0 FT.

THE CROSS SLOPE SHALL BE 2% MAXIMUM.


THE CLEAR WIDTH OF LANDINGS BLENDED TRANSITIONS, AND CURB RAMP, EXCLUDING FLARES, SHALL BE 4.0 FT. MINIMUM.

LANDING WIDTH SHALL MATCH THE ADJACENT SIDEWALK WIDTH, 5.0 FT MIN., UNLESS OTHERWISE APPROVED.

5.0 FT. BY 5.0 FT. IS MINIMUM LANDING DIMENSIONS PREFERRED. WHERE THE TURNING SPACE IS CONSTRAINED AT THE BACK-OF-SIDEWALK, THE TURNING SPACE SHALL BE 4.0 FT. MINIMUM BY 5.0 FT MINIMUM. THE 5.0 FT DIMENSION SHALL BE PROVIDED IN THE DIRECTION OF THE RAMP RUN.

THE SLOPE PARALLEL TO THE CURB SHALL NOT EXCEED 2% AT YIELD OR STOP CONTROLLED INTERSECTIONS. AT UNCONTROLLED INTERSECTIONS, THE SLOPE PARALLEL TO THE CURB MAY BE UP TO 5%. AT MIDBLOCK CROSSINGS, THE SLOPE PARALLEL TO THE CURB MAY MATCH THE ROAD GRADE.

TYPICAL PARALLEL CURB RAMP
ACCORDING TO PROWAG REQUIREMENTS
NOT TO SCALE - ROTATED TO FIT



SIDEWALK OR OTHER TRAVERSABLE SURFACE

DETECTABLE WARNING SURFACE (DWS)

LEVEL AREA (TURNING SPACE/LANDING)
2% MAX. SLOPE IN ANY DIRECTION



CROSS SLOPE 2.0% MAX.



RUNNING SLOPE 8.3% MAX.




COUNTER SLOPE 5.0% MAX. ASCENDING OR DESCENDING



4'X4' CLEAR SPACE



REQUIRED DESIGN ELEVATIONS
SLOPES TO BE SHOWN WITH DESIGN



TYPICAL DIAGONAL CURB RAMP
REQUIRES CITY APPROVAL FOR CONSTRUCTION
ACCORDING TO PROWAG REQUIREMENTS
NOT TO SCALE - ROTATED TO FIT

NOTE: DIAGONAL CURB RAMP ALTERNATE IS ONLY ALLOWED WHEN DIRECTIONAL RAMP ARE NOT POSSIBLE AND MUST BE APPROVED BY THE CITY ENGINEER.

DRAWN A.J.D.
DIV. ROADWAY
REV. DATE



CITY OF BEND

CITY OF BEND
STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL PARALLEL CURB RAMP

SCALE NTS

DATE 12/10/21


APPR

STD DWG R-6B


01/14/2022 1:14:01 PM

CROSSWALK MARKING.
STYLE VARIES, SEE
PLANS.

RAMPS TO BE FULLY
LOCATED WITHIN CROSS
WALK MARKING



CROSS WALK - CURB RAMP ORIENTATION
NOT TO SCALE



NOTE: IN AREAS WITH UNIT PAVER CROSS WALKS, REMOVE EXISTING
PAVERS, AND RE-INSTALL AT GRADES TO ACHIEVE THESE REQUIREMENTS.

TYPICAL RAMP / ASPHALT PATCH SECTION
NOT TO SCALE

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND
STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

CURB RAMP DETAILS


SCALE NTS

DATE 12/10/21


APPR

STD DWG R-6C

INSTALLATION IN NEW CONSTRUCTION



SECTION A-A



ANCHOR BASE DETAIL

NOTES:

1. USE PSST ANCHOR BASE FOUNDATION FOR ALL SIGN LOCATIONS OTHER THAN IN MEDIANS AND ROUNDABOUT SPLITTER ISLANDS PER STD DWG R-7A.
2. ANCHOR BASE HOLES AND BOTTOM OF ANCHOR BASE SHALL BE COVERED SO THAT CONCRETE DOES NOT SEEP INTO ANCHOR BASE DURING SETTING
3. BASE SHOULD BE SET SEPARATELY FROM POST WITH ANCHOR BOLT IN BASE BOTTOM ONLY
4. POST SHOULD BE ABLE TO SLIDE FREELY WHEN RIVET IS REMOVED
5. FOR LARGE SIGNS THAT EXCEED WINDLOADS 2 1/2" POSTS MAY BE APPROVED BY CITY ENGINEER

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PSST ANCHOR BASE FOUNDATION

SCALE NTS


DATE 12/10/21

APPR

STD DWG R-7

SIGN POST SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS.

3"x3"x7 GUAGE ANCHOR TUBE WELDED TO BOTTOM SLIP BASE.



$\frac{3}{8}$ " BOLT WITH 2 FLATWASHERS, AND 1 NUT. (2 REQUIRED)

$\frac{1}{2}$ " BOLT WITH 2 SLEEVES, 2 FLATWASHERS, AND NUT. (3 REQUIRED)

TOP SLIP BASE PLATE
TEFLON GASKET
BOTTOM SLIP BASE PLATE

NUT
WASHER

PERFORATED STEEL SQUARE TUBE (PSST)

WASHER
 $\frac{3}{8}$ " BOLT

NUT
WASHER
TOP SLIP BASE PLATE

BOLT SLEEVE
TEFLON GASKET
BOLT SLEEVE
BOTTOM SLIP BASE PLATE

WASHER
 $\frac{1}{2}$ " BOLT


SLIP BASE EXPLODED VIEW

NO SCALE

3"x3"x7 GUAGE ANCHOR TUBE WELDED TO BOTTOM SLIP BASE.

PLAN
NO SCALE

DIRECTION OF TRAVEL



NOTES:

1. USE PSST SLIP BASE FOUNDATION FOR SIGNS INSTALLED IN MEDIANS AND ROUNDABOUT SPLITTER ISLANDS.
2. MATERIAL GRADE FOR BASE HARDWARE CONNECTION SHALL BE ACCORDING TO THE MANUFACTURER'S RECOMMENDATION AND BASED ON CRASH TESTING.
3. SLIP BASE STEEL SHALL BE HOT DIPPED GALVANIZED OR APPROVAL EQUAL.
4. FOOTING CONCRETE SHALL BE COMMERCIAL GRADE CONCRETE (FC=3000PSI) PER SPECIFICATION 00440. THE CGC MIXTURE MAY BE ACCEPTED AT THE SITE OF PLACEMENT ACCORDING TO 00440.14.
5. ALL SLIP BASES SHALL BE PRE-ASSEMBLED BY THE MANUFACTURER AND SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS.
6. SLIP BASE DETAILS SHOWN ARE NOT FOR A SPECIFIC MANUFACTURER AND ARE ONLY SHOWN TO CONVEY GENERAL PIECES OF A SLIP BASE SYSTEM. SPECIFIC SLIP BASE MATERIAL WILL BE ACCORDING TO THE MANUFACTURER'S DOCUMENTATION.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


PSST SLIP BASE FOUNDATION

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-7A



STRIPING DETAIL FOR PAVED PATH OR ACCESS ROAD

* Length of approach line varies by
location, where possible, 25' min.

NOTES:

1. POSTS OR BOLLARDS SHALL BE SET BACK BEYOND THE CLEAR ZONE OF THE ADJACENT STREET OR BE OF A BREAKAWAY DESIGN. THE POST SHALL BE PERMANENTLY REFLECTORIZED FOR NIGHTTIME VISIBILITY AND PAINTED WHITE FOR IMPROVED DAYTIME AND NIGHT TIME VISIBILITY.
2. ON PAVED PATHS OR ACCESS ROADS, APPLY PAVEMENT MARKINGS PER STRIPING DETAIL.

DRAWN	AJD
DIV	ROADWAY
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

REMOVABLE POST AND MARKINGS


SCALE NTS

DATE 12/10/2021

APPR

STD DWG R-7B


01/14/2022 1:14:01 PM



SIGN LOCATION	DIMENSIONS												
	A	B	C	D	E	F	G	H	J	K	L	M	N
LOCAL	VAR	8	0.375	2	4C	3C	3	3 MIN	3	1	1.75	2.25	2.75
COLLECTOR/ ARTERIAL \leq 40MPH	VAR	12	0.5	3	6C	4.5C	5	4.5 MIN	4.5	1.5	2.75	3.25	4.75
COLLECTOR/ ARTERIAL $>$ 40 MPH	VAR	18	0.75	5	8C	6C	7.67	5.33 MIN	6	1.875	5	5	7.67
OVERHEAD	VAR	24	1	6	12C	9C	10	9 MIN	9	2.25	5	6	9.50





NOTES:

- SIGNS INSTALLED ALONG PUBLIC STREETS SHALL BE FABRICATED AND INSTALLED TO CONFORM TO THE MUTCD AND CITY OF BEND SPECIFICATIONS.
- UNLESS OTHERWISE SPECIFIED, STREET NAME SIGNS SHALL BE FABRICATED AS FOLLOWS:
 - SIGN SUBSTRATE: SHEET ALUMINUM (GAUGE 0.80 FOR GROUND-MOUNT) WITH ROUNDED CORNERS
 - RETRO-REFLECTIVE SHEETING: GREEN BACKGROUND WITH WHITE LEGEND, USING HIP/TYPE G FOR GROUND-MOUNTED SIGNS, AND DIAMOND GRADE/TYPE G2 FOR SIGNS MOUNTED OVERHEAD;
 - LETTERING SHALL BE LOWER-CASE WITH INITIAL UPPER-CASE LETTERS;
 - SERIES C2000 FONT, WITH LETTERING AND LETTER SPACING PER THE FEDERAL HIGHWAY ADMINISTRATION'S STANDARD ALPHABETS AS SHOWN IN THE CURRENT EDITION OF THE STANDARD HIGHWAY SIGNS AND PAVEMENT MARKINGS MANUAL. (* EXCEPT FOR OVERHEAD SIGNS, WHERE SIGNS EXCEED 36" LONG, SERIES B2000 FONT SHALL BE USED);
 - BOTTOM STREET SIGNS (CLOSEST TO THE REGULATORY/STOP SIGN) SHALL BE TWO SINGLE-SIDED WITH PREDRILLED HOLES. SIGNS SHALL BE RIVETED BACK TO BACK ON THE SQUARE TUBE POST, CENTERED ON THE POST.
 - BOTTOM STREET SIGNS SHALL BE USED FOR SIDE STREET.
 - TOP STREET SIGN SHALL BE DOUBLE SIDED. TOP SIGN USED FOR MAINLINE STREET.
- ALL SIGNS SHALL BE REVIEWED AND APPROVED BY THE CITY OF BEND ENGINEERING DEPARTMENT PRIOR TO FABRICATIONS AND INSTALLATION.
- TYPICAL INSTALLATION INCLUDES 2-INCH SQUARE TUBE CAPS WITH 90-DEGREE ANGLE BRACKETS ON 2-INCH PERFORATED SQUARE TUBE STEEL POSTS. USE 5- OR 6-INCH BLADE MOUNTS FOR SIGNS LESS THAN 36" WIDE; 12-INCH MOUNTS FOR SIGNS 36-INCHES OR WIDER OR OVER 6-INCHES HIGH. SEE STANDARD DRAWINGS R-7 AND R-9.
- SIGN WIDTHS VARY WITH LEGEND. WHERE SITE CONSTRAINTS LIMIT AVAILABLE SPACE, REDUCED LETTER HEIGHT, FONT STYLE, LINE SPACING, OR EDGE SPACING WILL BE CONSIDERED. REDUCTIONS IN SPACING BETWEEN LETTERS OR WORDS IS NOT PERMITTED.
- WHERE PRIVATE STREETS INTERSECT WITH PUBLIC STREETS, INSTALL A BLACK ON YELLOW PRIVATE DR SIGN WITH 4-INCH CAPITAL LETTERS (ODOT SIGN POLICY SIGN #OW14-3) DIRECTLY BELOW THE PRIVATE STREET NAME SIGN (OR ON A SEPARATE POST, IF NOT AT AN INTERSECTION).
- FOR ADDITIONAL INFORMATION, REFER TO MUTCD SECTION 2A AND 2D, AND CITY OF BEND TECHNICAL SPECIFICATION SECTION 00940.
- CONFIRM SIGN SIZE WITH CITY ENGINEER FOR SIGNS ON EXISTING TRAFFIC SIGNAL POLES OR MAST ARMS.

DRAWN AJD			 CITY OF BEND	CITY OF BEND			SCALE NTS
DIV ROADWAY				STANDARD DRAWING			DATE 12/10/21
REV	DATE	APPR		710 NW WALL ST., BEND, OREGON 97701			APPR
				STANDARD STREET NAME SIGNS			STD DWG R-8

STANDARD STREET NAME SIGNS

01/14/2022 1:14:01 PM



NOTES:

1. SET TO MUTCD SPECS
2. SEE R-8 FOR COB STREET NAME SIGN REQUIREMENTS.
3. CHECK THAT SIGN IS NOT OBSCURED BY VEGETATION, TRIM IF NEEDED.
4. INSTALL ALL SIGNS WITH 5/16"X3/8" DRIVE RIVETS

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STANDARD STREET SIGN PLACEMENT


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-9

TABLE A	
PIPE DIA (IN)	"A" (IN)
4	10
6	10
8	10
10	10
12	12
15	12
18	16
21	16
24	18
30	18
36	24
42	24
48	24
54	24
60	24
66	24
72	24



NOTES:

1. ALL COMPACTION TO COMPLY WITH SPECIFICATION SECTION 00330.43 AND 00405.46(c).
2. A FRANCHISE UTILITY THAT IS A SINGLE CONDUIT AND IS 4 INCHES IN DIAMETER OR LESS MAY BE CENTERED IN A 12-INCH WIDE TRENCH PROVIDED THAT THE TRENCH CAN ACCOMMODATE THE COMPACTION EQUIPMENT. TRENCH PATCH SHALL BE IN ACCORDANCE WITH STD DWG R-11 WHERE THE TEE PATCH SHALL NOT BE LESS THAN 12 INCHES ON BOTH SIDES OF THE TRENCH. OVERALL WIDTH MAY BE REDUCED FROM 4 FEET, BUT IN NO CIRCUMSTANCES RESULT IN TEE PATCHES LESS THAN 12 INCHES AND AN OVERALL MINIMUM WIDTH OF 3 FEET.
3. CLASS E - CLSM, MAY BE ALLOWED FOR TRENCH BACKFILL WHERE COMPACTION CANNOT BE MET DUE TO THE PRESENCE OF EXISTING UTILITIES

DRAWN A.JD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL TRENCH SECTION


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-10

01/14/2022 1:14:02 PM



NOTES:

1. ALL COMPACTION TO COMPLY WITH CITY OF BEND STANDARDS
2. ALL FRANCHISE UTILITIES SHALL BE INSTALLED IN UL APPROVED SCHEDULE 40 PVC CONDUIT WITH SCHEDULE 40 PVC FITTINGS UNLESS OTHERWISE APPROVED.
3. UTILITY SIZES AND LOCATION SHALL BE DETERMINED BY THE UTILITY COMPANY. LOCATION TO BE SHOWN AND APPROVED BY CITY WITH A RIGHT OF WAY (ROW) PERMIT.
4. WHERE STORM SWALES ARE PROPOSED WITHIN THE LANDSCAPE STRIP, FRANCHISE UTILITIES SHALL BE INSTALLED OUTSIDE OF THE SWALE AREA.
5. TOP SOIL LAYER TO BE COMPACTED TO 90% MAX DENSITY. WHERE SIDEWALK IS PLACED OVER FRANCHISE UTILITY TRENCH, NO TOP SOIL SHALL BE PLACED AND SIDEWALK TO BE CONSTRUCTED TO COMPLY WITH CITY STANDARDS R-4A AND R-4B
6. STANDARD SHOWN FOR NEW CONSTRUCTION. MODIFICATIONS SHALL BE MADE WHEN WITHIN EXISTING DEVELOPMENTS WHERE APPROVED BY THE CITY ENGINEER.
7. UTILITIES OUTSIDE THE RIGHT OF WAY SHALL BE WITHIN A PUBLIC UTILITIES EASEMENT (PUE). BACKFILL AND INSTALLATION REQUIREMENTS STILL COMPLY WITH THE PUE.
8. NO SWALES OR SURFACE STORMWATER DRAINAGE FACILITIES ARE PERMITTED OVER FRANCHISE UTILITIES.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

FRANCHISE UTILITY JOINT TRENCH


SCALE NTS

DATE 12/10/2021

APPR

STD DWG R-10A

01/14/2022



NOTES:

1. SURFACE RESTORATION IN EXISTING PAVEMENT TO COMPLY WITH SPECIFICATION 00495.
2. UNIMPROVED AREA CONSISTS OF ANY PORTION OF THE ROW THAT HAS NOT BEEN IMPROVED TO A CITY STANDARD AND CONSISTS MOSTLY OF NATIVE VEGETATED AREAS. UNIMPROVED AREAS ALSO INCLUDE AREAS WITHIN THE LANDSCAPE STRIP AND PUEs.
3. ALL EXISTING AC OR PCC PAVEMENT SHALL BE SAWCUT PRIOR TO REPAVING. CONCRETE SHALL BE CUT AND REPLACED TO THE NEAREST JOINT(S).
4. CONCRETE PAVEMENT SHALL BE REPLACED WITH CONCRETE TO A MINIMUM THICKNESS OF 6" OR TO THE THICKNESS OF REMOVED PAVEMENT, WHICHEVER IS GREATER
5. PLACE ACP A MINIMUM THICKNESS PER R-1 OR TO THE THICKNESS OF REMOVED PAVEMENT, WHICHEVER IS GREATER. PLACE ACP IN 2" MAX LIFTS.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


TRENCH SURFACE RESTORATION

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-11



X DIMENSION:


- MEDIAN/ALL ADJACENT TO TRAVEL LANE = 6"
- ONLY BACK SIDE OF SIDEWALK OR SEPARATE FROM TRAVEL LANE = 4"
- TRUCK APRON = 9"


Y DIMENSION:


- MEDIAN/ALL ADJACENT TO TRAVEL LANE = 6"
- ONLY BACK SIDE OF SIDEWALK OR SEPARATE FROM TRAVEL LANE = 4"
- TRUCK APRON = 6"


NOTE:

1. STAMPED CONCRETE SURFACE TEXTURE PATTERN SHALL BE BRICKFORM "FLAGSTONE" TM-700) WITH SAWCUT GROOVE JOINTS 1/3 CONCRETE DEPTH.
2. GLAZE AND SEAL PER MANUFACTURERS SPECS.
3. INTEGRAL COLOR: DAVIS SPANISH GOLD (3 LBS. #5084)
4. RELEASE COLOR: DAVIS DARK GREY (#860)

DRAWN AJD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV ROADWAY			DATE 12/10/21
REV		PATTERNED COLORED CONCRETE DETAIL	APPR
DATE			STD DWG R-24



DRAWN AJD		 CITY OF BEND	CITY OF BEND		SCALE NTS
DIV ROADWAY			STANDARD DRAWING		DATE 12/10/21
REV	DATE		710 NW WALL ST., BEND, OREGON 97701		APPR
			MEDIAN END DETAIL		STD DWG R-25



NOTES:

1. NO PARKING WITHIN THE CLEAR VISION OR 20 FEET OF THE INTERSECTION, WHICHEVER IS GREATER.
2. AS REQUIRED BY THE CITY ENGINEER, INSTALL YELLOW 36" TALL YELLOW SURFACE MOUNTED TUBULAR MARKERS, PER SPECIFICATION SECTION 00856 FOR PLOW SIGNAGE AT CURB EXTENSIONS.
3. USE LOW GROWING VEGETATION FOR BIORETENTION SWALES/ PLANTERS LOCATED IN CURB EXTENSIONS.
4. CURB RETURNS TO BE CONSTRUCTED PER DESIGN STANDARD.
5. YELLOW CURB PAINT ON RETURNS IS REQUIRED IN COMMERCIAL AND HIGH DENSITY RESIDENTIAL AREAS

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

LOCAL STREET CURB EXTENSIONS


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-26

01/14/2022 1:14:02 PM



NOTES:

1. PARKING BAYS SHALL BE DESIGNED OUTSIDE THE CLEAR VISION OF THE INTERSECTION. PARKING WILL BE PERMITTED IF CLEAR VISION AND SIGHT DISTANCE AS ANALYZED AS SAFE BY A PROFESSIONAL ENGINEER.
2. PARKING BAYS ON COLLECTORS ARE PERMITTED AS DIRECTED BY THE DEVELOPMENT CODE.
3. NO MORE THAN 10 PARKING BAYS WILL BE PERMITTED TOGETHER. TERMINATION OF BAYS WILL BE FOR VEGETATION PLANTING, UTILITY INSTALLATION (FRANCHISE UTILITY VAULTS, STORM FACILITIES, ETC).
4. PARKING IS NOT PERMITTED WITHIN THE INTERSECTION'S CLEAR VISION AND SIGHT DISTANCE AS DETERMINED BY AASHTO REQUIREMENTS AND ENGINEER REVIEW.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

COLLECTOR / LOCAL INTERSECTION


SCALE NTS

DATE 12/10/21


APPR

STD DWG R-27


01/14/2022 1:14:02 PM



ANGLED PARKING PLAN



**ACCESS AISLE
ANGLE LAYOUT**




LEGEND	DIMENSIONS (INCHES)		
	A	B	C
MINIMUM	28	24	3
STANDARD	41	36	4


PAVEMENT MARKING LAYOUT

NOTE:

1. THIS IS ONE EXAMPLE OF AN ACCESSIBLE PARKING CONFIGURATION. REFER TO ODOT ACCESSIBLE PARKING STANDARDS FOR ADDITIONAL DETAILS AND OTHER CONFIGURATIONS.
2. ALL SIGNS AND PLACEMENT SHALL CONFORM TO ODOT STANDARDS.



PARALLEL PARKING PLAN



DRAWN	AJD
DIV	ROADWAY
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

ACCESSIBLE PARKING - ANGLE

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-29

01/14/2022

PARABOLIC CROWN
(TOLERANCE 0.5"±)

HOT POURED
JOINT SEAL

2.0"

4'-0" GRIND

7'-0"

3.0"

2.9"

2.8"

2.4"

2.0"

1.5"

0.8"

HOT POURED
JOINT SEAL

2.0"

12"

12"

12"

12"

12"

12"

12"

12"


LEVEL 3, 1/2" DENSE HOT MIX ASPHALT

SECTION
PROFILE VIEW



2' (TYP), OR 4'
WHERE NO OTHER
ACCESSIBLE ROUTE

CURB



14'-0"

STREET CENTERLINE
OR CENTERLINE STRIPE

CL


HOT POURED JOINT SEAL
ENTIRE PERIMETER

CURB



STORMWATER DRAINAGE
SHALL BE MAINTAINED TO
AN APPROVED DISCHARGE.


PLAN VIEW



W	A	B	A	B
28'	12'	11'	7'	12'
30'	12'	11.5'	7'	12.5'
32'	13'	12'	7'	13'
34'	13'	12.5'	7'	14'
36'	13'	13'	7'	15'

PARKING
BOTH
SIDES

PARKING
ONE SIDE



CROSS
SECTION AT
CURB

NOTES:

1. SPEED HUMPS ARE ONLY PERMITTED IN SELECT LOCATIONS. REFER TO CITY DESIGN STANDARDS.
2. WHERE SPEED HUMP IS A RETRO-FIT TO AN EXISTING ROAD:
 - 2.1. GRIND / KEY-IN PERIMETER TO THE DIMENSIONS SHOWN OR AS DIRECTED BY THE ENGINEER.
 - 2.2. APPLY TACK COAT TO ALL EXISTING SURFACES WHERE SPEED HUMP WILL BE IN CONTACT.
3. HOT POURED JOINT SEAL THE ENTIRE PERIMETER AFTER INSTALLATION.
4. ALL VERTICAL DIMENSIONS HAVE A REQUIRED MAXIMUM TOLERANCE OF +/- 1/4".
5. THE DISTANCE BETWEEN CURB AND EDGE OF THE SPEED HUMP VARIES. SEE ENGINEERED PLANS.
6. PAVEMENT MARKINGS ON SPEED BUMP SHALL BE INSTALLED CONCURRENTLY WITH THE ASPHALT STRUCTURES. PAVEMENT MARKINGS SHALL BE THERMO-PLASTIC.
7. PAVEMENT MARKINGS SHALL BE INSTALLED BEFORE OPENING ANY LANE TO TRAFFIC THAT IS OCCUPIED BY A NEW SPEED BUMP.
8. SPEED HUMPS ARE NOT PERMITTED IN ACCESSIBLE ROUTES OR WHERE IN CONFLICT WITH DRIVEWAYS.

DRAWN A.JD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701



SPEED HUMPS AND SHARROW PLACEMENT

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-32



NOTES:

1. RAISED CROSSWALKS ARE ONLY PERMITTED IN SELECT LOCATIONS. REFER TO CITY DESIGN STANDARDS.
2. HOT POURED JOINT SEAL THE ENTIRE PERIMETER AFTER INSTALLATION.
3. PAVEMENT MARKINGS ON RAISED CROSSWALKS SHALL BE THERMO-PLASTIC.
4. PAVEMENT MARKINGS SHALL BE INSTALLED BEFORE OPENING ANY LANE TO TRAFFIC THAT IS OCCUPIED BY A NEW SPEED BUMP.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

RAISED CROSSWALK



SCALE NTS

DATE 12/10/21


APPR

STD DWG R-33

01/14/2022 14:02 PM



R1-2
30"X30"



R6-5P
30"X30"

NOTES:

1. STANDARD IS YIELD CONTROL. TWO-WAY STOP MAY BE CONSIDERED FOR CIRCLES WITH INSUFFICIENT CIRCULATING DIAMETER FOR CROSSWALK OR SIGHT DISTANCE OBSTRUCTION THAT CANNOT BE MITIGATED

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


TRAFFIC CIRCLE

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-34



RECTANGULAR RAPID FLASHING BEACON SYSTEM PSST INSTALLATION

NOTES:

1. REMOVE SOLAR EQUIPMENT IF USING COMMERCIAL POWER
2. ADD RADIO NETWORK CONTROLLER FOR WIRELESS EQUIPMENT IF NEEDED
3. USE SCHOOL CROSSING (S1-1) FOR DESIGNATED SCHOOL CROSSING

DRAWN	AJD
DIV	ROADWAY
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

RECTANGULAR RAPID FLASHING BEACON

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-35

01/14/2022 1:14:02 PM

W




4" WHITE LINE

W-2




8" WHITE LINE

WB




4" WHITE BROKEN LINE

DLL-2



8" WHITE DOTTED LANE LINE


WD



4" WHITE DOTTED LINE

For lane extensions


WD-2



8" WHITE DOTTED LINE

For lane extensions


WRAB



8" WHITE DOTTED ROUNDABOUT
CIRCULATING LINE

INSTALL AS TYPE B-HS PREFORMED
THERMOPLASTIC

NDW



NARROW DOUBLE NO-LANE CHANGE
TWO 4" WHITE LINES

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PAVEMENT MARKINGS - WHITE

SCALE NTS


DATE 12/10/21

APPR


STD DWG R-40

01/14/2022 1:14:02 PM

YB




4" YELLOW LINE



4" YELLOW BROKEN LINE


YD



4" YELLOW DOTTED LINE


For lane extensions

D




DOUBLE NO-PASS
TWO 4" YELLOW LINES

ND




NARROW DOUBLE NO-PASS
TWO 4" YELLOW LINES

NPR




NO-PASS RIGHT
4" YELLOW LINES

NPL



NO-PASS LEFT
4" YELLOW LINES

TWL



TWO-WAY LEFT TURN
4" YELLOW LINES

SEE R-44 FOR ARROW PLACEMENT

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PAVEMENT MARKINGS - YELLOW


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-41


07/14/2022 1:14:03 PM



STANDARD CROSSWALK TWO 1' WHITE BARS

Install per Standard Drawing R-47


S



STOP BAR 1' WHITE BAR

Install stop bar in Thermoplastic. Install per Standard Drawing R-45


CW-SC



STAGGERED CONTINENTAL CROSSWALK 2' WHITE BARS

Install per standard drawing R-47; Install as Type B-HS preformed thermoplastic;
Install at uncontrolled approach


TS-(X)



TRANSVERSE SHOULDER BARS 1' WHITE BARS AT 20' SPACING

X = 20', Typical
(40' spacing may be used where median length exceeds 200')


TM-(X)



TRANSVERSE MEDIAN BARS 1' YELLOW BARS AT 20' SPACING

X = 20', Typical
(40' spacing may be used where median length exceeds 200')


BUF



2' BUFFER BETWEEN BIKE LANE AND PARKING BUFFER STRIPE

Install buffer stripes in thermoplastic / horizontal stripes parallel with traffic in paint

BUFP



PARKING PROTECTED BIKE LANE

DRAWN A.J.D.
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PAVEMENT MARKINGS

SCALE NTS


DATE 12/10/21

APPR

STD DWG R-42A

CN


01/14/2022 1:14:03 PM



ONLY (white)

Center marking within lane width
Install in Type B - HS Preformed Thermoplastic
For letter proportion details, see current version of FHWA Standard Highway Signs


SCH



SCHOOL (white)

Center marking within lane width
Install in Type B - HS Preformed Thermoplastic
For letter proportion details, see current version of FHWA Standard Highway Signs
Install at school speed zone sign on arterial and collector roads

E-SA




ELONGATED STRAIGHT ARROW (white)

For arrow proportion details, see current version of FHWA Standard Highway Signs
Install in Type B - HS Preformed Thermoplastic
Center marking within lane width

E-LA


E-RA



ELONGATED TURN ARROW (white)

For arrow proportion details, see current version of FHWA Standard Highway Signs
Install in Type B - HS Preformed Thermoplastic
Center marking within lane width
Use E-LA for Left Turn and E-RA for right turn.


E-LSA



ELONGATED LEFT TURN STRAIGHT ARROW (white)

For arrow proportion details, see current version of FHWA Standard Highway Signs
Install in Type B - HS Preformed Thermoplastic
Center marking within lane width


E-RSA



ELONGATED RIGHT TURN STRAIGHT ARROW (white)


For arrow proportion details, see current version of FHWA Standard Highway Signs
Install in Type B - HS Preformed Thermoplastic
Center marking within lane width

P



ON-STREET PARKING DETAIL (white)

SB



SPEED BUMP MARKING (WHITE)

Install in Type B - HS Preformed Thermoplastic
Center marking within lane width

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PAVEMENT MARKINGS


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-42B


133/14/2022 1:14:03 PM



BIKE LANE STANDARD STENCIL (white)

Center marking within lane width
For proportion details, see current version of FHWA Standard Highway Signs


B



BIKE SYMBOL (WHITE)

Install in Type B - HS Preformed Thermoplastic
Center marking within lane width


BR



BIKE RIGHT TURN STENCIL (white)

Center marking within lane width
For proportion details, see current version of Standard Highway Signs


BL



BIKE LEFT TURN STENCIL (white)

Center marking within lane width
For proportion details, see current version of Standard Highway Signs


BRS



BIKE RIGHT TURN STRAIGHT STENCIL (white)

Center marking within lane width
For proportion details, see current version of Standard Highway Signs


BLS



BIKE LEFT TURN STRAIGHT STENCIL (white)

Center marking within lane width
For proportion details, see current version of Standard Highway Signs

BD



BIKE DETECTOR (WHITE)

Install in Type B - HS Preformed Thermoplastic
Place marking in optimal location for bicycle to actuate the traffic signal.

DRAWN **AJD**
DIV **ROADWAY**
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PAVEMENT MARKINGS - BIKE


SCALE **NTS**

DATE **12/10/21**

APPR


STD DWG **R-43**

6/14/2022 1:14:03 PM




SHARROWS (WHITE)

Install in Type B - HS Preformed Thermoplastic
Locate marking per R-32
Arrow may be turned in direction of travel.




RIGHT TURN SHARROWS (WHITE)

Install in Type B - HS Preformed Thermoplastic
Locate marking per R-32




LEFT TURN SHARROWS (WHITE)

Install in Type B - HS Preformed Thermoplastic
Locate marking per R-32




BIKE MARKING EXTENSION THROUGH INTERSECTION

* 6' or bike lane width



COMMON PATH WAYFINDING ARROW

Black inner circle / Green ring / White arrow/bike symbol
Arrow may be turned in direction of travel.



YELLOW MARKING OBSTRUCTION IN PATH

DRAWN **AJD**
DIV **ROADWAY**
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PAVEMENT MARKINGS - BIKE


SCALE **NTS**

DATE **12/10/21**

APPR

STD DWG **R-43A**

01/14/2022 1:14:03 PM




General Notes:


- Center pavement marking legends within the lane.
- Placement of lane use arrows with respect to the 8" wide white line (W-2) channelization shown in details "A", "B" and "C" apply to both left and right turn lanes.
- When used for a short turn lane ($<40'$), the 2nd (downstream) arrow may be omitted.
- An ONLY symbol is only required where a through lane approaching an intersection becomes a mandatory turn lane.

** When L is greater than 200', install 3rd lane use arrow at the midpoint of the turn lane.

To be accompanied by Standard Dwg. Nos. R-40 thru R-43


DRAWN AJD			CITY OF BEND	CITY OF BEND		SCALE NTS
DIV ROADWAY				STANDARD DRAWING		DATE 12/10/21
REV	DATE			710 NW WALL ST., BEND, OREGON 97701		APPR
				TURN LANE MARKING LAYOUT		STD DWG R-44

01/14/2022 1:14:03 PM



**GREEN SUPPLEMENTED BICYCLE LANE
SOLID LANE**


**GREEN SUPPLEMENTED BICYCLE LANE
DOTTED LINE EXTENSION**



TYPICAL GREEN SUPPLEMENTED BICYCLE LANE ACROSS AN ADDED RIGHT TURN LANE TAPER

POSTED SPEED (MPH)	A* (FT.) (MIN)
35 AND LESS	9
40	30
45	50

Add 20 ft if BS does not precede GRN



TYPICAL GREEN SUPPLEMENTED BICYCLE LANE AT A DROPPED RIGHT TURN LANE

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

INTERSECTION BIKE SAFETY

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-44A


General Notes:

- Where a curb clearly defines the roadway edge in the taper area, the edge line shown may be omitted in the taper area as determined by engineer judgement.
- Motor vehicle speed adjacent to bicycle lane.


POSTED OR 85TH PERCENTILE SPEED (MPH) ²	d (FT)	L (ft)
20	128	L=WS
25	152	
30	176	
35	184	
40	192	
45+	200	

WHERE:

L = taper length
W = width of bicycle lane being reduced (ft)
"d" distances are for level roads.
Corrections should be made for grades.




END OF BIKE LANE



General Note:

Install bike lane stencil to avoid right turning vehicle wheel tracks.

INSTALLATION OF BIKE LANE STENCILS FOLLOWING INTERSECTIONS



BUFFER BIKE LANE IN CONFLICT AREA
(FOR HIGH VOLUME COMMERCIAL DRIVEWAYS)

To be accompanied by Standard Dwg. Nos. R-40 thru R-43 and R-44A

DRAWN	AJD
DIV	ROADWAY
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

BIKE LANE MARKINGS



SCALE NTS

DATE 12/10/21

APPR

STD DWG R-44B

01/14/2022 1:14:03 PM



DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

BIKE LANE MARKINGS

SCALE NTS




DATE 12/10/21

APPR

STD DWG R-44C

01/14/2022 1:14:03 PM

- 1) Stop bar required at stop control approaches on arterials and collector streets
- * Stop bar shall be placed as near as possible to the intersecting traveled way. Locate stop bar 4' min. to 30' max. in advance of the extended fog line, edge of pavement, or curb face. Minimum stop bar distance may need to be increased, depending on location of pedestrian ramps (see Detail "A") and/or vehicle turn radii (see Detail "B"). Field verify sight distance and truck turning movements. Stop bar not required at local/local intersections.



To be accompanied by Standard Dwg. Nos. R-40 thru R-43

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND
STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

INTERSECTION PAVEMENT MARKING LAYOUT


SCALE NTS

DATE 12/10/21

APPR

STD DWG R-45


01/14/2022 1:14:03 PM



STAGGERED CONTINENTAL LAYOUT

General Note:

1. Install crosswalk bars such that the throat of the ADA ramp is entirely within crosswalk markings, or 5' back of extended fog line, edge of pavement, or curb face.



STANDARD CROSSWALK BARS AT 4-WAY CONTROLLED INTERSECTION

To be accompanied by Standard Dwg. Nos. R-40 thru R-43

DRAWN AJD	
DIV ROADWAY	
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

CROSSWALK MARKINGS

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-47


01/14/2022 1:14:03 PM

TRANSITION AT EDGE WITH NATIVE
TOPSOIL AND NATIVE GRASS SEED
SUITABLE TO THE SITE

PAVED TRAIL
3" ASPHALT 4" BASE COURSE OF
5/8" MINUS AGGREGATE.

CROSS SLOPE PATH TO
DRAIN AT 1.5%

IF TRAIL IS USED AS
SERVICE ACCESS, INCREASE
PAVING THICKNESS



NOTES:

1. TRAIL SHALL BE PAVED IN THE RIGHT-OF-WAY OR ADJACENT TO STREETS. OUTSIDE OF THE RIGHT-OF-WAY TRAIL MAY BE AGGREGATE AS APPROVED.
2. PRIMARY TRAILS ARE TYPICALLY FACILITIES OUTSIDE OF THE PUBLIC RIGHT-OF-WAY THAT ARE OWNED AND MAINTAINED BY THE BEND PARKS AND RECREATION DISTRICT OR PRIVATELY. (SEE STANDARD CROSS-SECTIONS FOR CITY SHARED USE PATHS IN THE RIGHT-OF-WAY.)
3. WHERE OUTSIDE OF RIGHT-OF-WAY, TRAIL EASEMENT DEDICATION IS REQUIRED INCLUDING A PUBLIC ACCESS EASEMENT AND UTILITY EASEMENT WHERE APPLICABLE.
4. PRIMARY TRAILS SHALL BE PAVED WITH CONCRETE OR ASPHALT. TRAIL ALIGNMENTS ARE ENCOURAGED TO MEANDER AND NOT BE DESIGNED AS FENCED CANYONS.
5. TRAILS WITHIN RIGHT-OF-WAY SHALL MEET PROWAG REQUIREMENTS. TRAILS OUT OF RIGHT-OF-WAY SHALL MEET THE REQUIREMENTS OF THE UNITED STATES ACCESS BOARD ACCESSIBILITY STANDARDS FOR FEDERAL OUTDOOR DEVELOPED AREAS.

DRAWN AJD
DIV ROADWAY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PRIMARY TRAIL

SCALE NTS

DATE 12/10/21

APPR

STD DWG R-48




Preliminary

01/14/2022 1:14:03 PM

CITY OF BEND STANDARD DRAWINGS

Sanitary (S)



NOTES:

1. FOR PRESSURE AND VACUUM SEWER MAINS ONLY, TRACER WIRE SHALL BE CENTERED ON TOP OF THE MAIN, AS CLOSE TO THE MAIN AS POSSIBLE. THE MAIN SHALL BE WRAPPED WITH MARKING TAPE A MIN OF 4 WRAPS PER 20 FEET OF MAIN. TRACER WIRE IS NOT REQUIRED ON GRAVITY SEWER MAIN.
2. PLACE TRACER WIRE ON GRAVITY, PRESSURE, AND VACUUM SEWER SERVICES. TRACER WIRE AND MARKING TAPE TO BE PER SPECIFICATION SECTION 00445.11.
3. TRANSITION FITTING SHALL BE A HARD COUPLER WHERE CHANGING PIPE MATERIAL
4. WHEN A SEWER LINE IS LOCATED ABOVE OR WITHIN 18" BELOW A WATERLINE, THE SEWER SHALL BE CONSTRUCTED WITH A MIN OF 20 LF OF AWWA C900 OR AWWA C905 PIPE CENTERED AT THE WATERLINE PER OAR 333-061-0050(9) AND BE APPROVED BY CITY/STATE.
5. WHEN INSTALLING A WATER LINE THAT CROSSES BELOW OR WITHIN 18 INCHES ABOVE A NON-POTABLE LINE, FOLLOW OAR 333-061-0050(9). ALL NON-POTABLE LINES SHALL BE TREATED AS "SEWER" LINES AS DESCRIBED IN OAR 333-061-0050(9).
6. COMPACTION SHALL MEET 00405.46(c) PER COB SPECIAL PROVISIONS

DRAWN AJD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


SEWER MAIN TYPICAL PROFILE

SCALE NTS

DATE 12/10/21


APPR


STD DWG S-1



(FOR USE ON MAINS LARGER THAN 12")

1. ALL TRENCHES TO CONFORM TO STD DWG R-10
2. SERVICES OFF NEW MAINS SHALL BE WYE OR TEE CONNECTIONS. SEE STD DWG S-2B FOR SERVICES OFF EXISTING MAINS
3. TRACER WIRE REQUIRED ON ALL SEWER / STORM SERVICES. MARKING TAPE SHALL BE INSTALLED AS SHOWN.
4. SEWER / STORM CONNECTION FROM THE PROPERTY LINE/ROW LINE TO THE CLEAN OUT NEAR THE BUILDING FOUNDATION REQUIRES A PLUMBING PERMIT.
5. WHEN A SEWER SERVICE IS LOCATED ABOVE OR WITHIN 18" BELOW A WATERLINE, THE SEWER SERVICE SHALL BE CONSTRUCTED WITH A MIN. 20 LF OF AWWA C900 OR AWWA C905 PIPE CENTERED AT THE WATERLINE PER OAR 333-061-0050(9).
6. STANDARD RESIDENTIAL SEWER SERVICES ARE 4"Ø. COMMERCIAL, INDUSTRIAL SEWER SERVICES ARE 6"Ø UNLESS OTHERWISE SIZED LARGER BY THE SITE'S ENGINEER.
7. WHERE A SERVICE CROSSES A NEW CURB, STAMP THE FACE OF CURB PER STD DWG R-3.
8. GRAVITY SEWER STANDARDS APPLY TO STORM SEWER MAINS.
9. MINIMUM 3' SECTIONS OF PIPE ARE REQUIRED BETWEEN FITTINGS.
10. ALL STORM SEWER LATERALS MUST COMPLY WITH CITY SEWER STANDARDS.


DRAWN AJD			CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701		SCALE NTS
DIV SANITARY					DATE 12/10/21
REV	DATE		APPR		
			STD DWG S-2A		
		CITY OF BEND	GRAVITY SEWER/STORM SERVICES ON NEW MAINS		



SEWER SADDLE
FOR USE ON MAINS SMALLER 12"


NOTES:

1. INSTALL SERVICE LATERAL PER STD DWG S-2A
2. CONNECTION TO EXISTING MAINS MAY BE CUT-IN FITTINGS PER STD DWG S-2A OR TAPS PER THIS DETAIL. PVC MAINS TO UTILIZE CUT IN FITTINGS.
3. SEWER SADDLE SHALL BE ROMAC STYLE "CB" OR APPROVED EQUAL.
4. INSTALL CONNECTION PER THE MANUFACTURER'S RECOMMENDATIONS.

DRAWN AJD	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV SANITARY			DATE 12/10/21
REV		GRAVITY SEWER/STORM SERVICE CONNECTION TO EXISTING MAIN	APPR
DATE			STD DWG S-2B

Preliminary

01/14/2022 1:14:04 PM



NOTES:

1. SEE STD DWG S-2A FOR GENERAL NOTES.

DRAWN AJD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701




GRAVITY SEWER/STORM CLEANOUT

SCALE NTS

DATE 12/10/21

APPR

STD DWG S-2C



SEWER MANHOLE LID DETAIL NTS

NOTES:

1. CITY SANITARY SEWER MANHOLE COVERS SHALL HAVE THE WORD "SEWER" CAST IN 2" RAISED LETTERS.
2. PRIVATE MANHOLE LIDS SHOULD NOT USE THE CITY OF BEND MANHOLE LID DETAIL.
3. HINGED MANHOLE LIDS ARE NOT PERMITTED UNLESS OTHERWISE APPROVED BY THE CITY ENGINEER.
4. LOCKS ARE TO BE USED ON THE LID WHEN THE LID IS LOCATED OUTSIDE A ROADWAY IF REQUIRED BY THE CITY ENGINEER.
5. MANHOLE LIDS SHALL BE PLACED OUTSIDE THE PATH OF TRAVEL ON SIDEWALKS AND DRIVEWAY APRONS.

DRAWN A.JD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


STANDARD SEWER MANHOLE RING & COVER

SCALE NTS

DATE 12/10/21



APPR

STD DWG S-3A





COMPOSITE COVER/FRAME ASSEMBLY NTS

FOR USE IN NON-TRAFFIC AREAS ONLY



APPLY WATER REPELLANT SEALER AROUND
ENTIRE FRAME CIRCUMFERENCE PRIOR TO
TIGHTENING THE CONCRETE ANCHORS.



APPLY WATER REPELLANT SEALER AROUND
ENTIRE FRAME CIRCUMFERENCE PRIOR TO
TIGHTENING THE CONCRETE ANCHORS.

DRAWN	AJD
DIV	SANITARY
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

COMPOSITE MANHOLE FRAME AND COVER


SCALE NTS

DATE 12/10/21

APPR

STD DWG S-3B

STD DWG S-3C



GENERAL NOTES:

1. FLOW CHANNELS DEVIATING FROM THE STANDARD CHANNELS REQUIRE A DETAIL FOR APPROVAL FROM THE ENGINEER
2. WIDTH OF CHANNEL SHOULD MATCH THE INSIDE DIAMETER OF INCOMING AND OUTGOING PIPES.
3. CHANNEL LINING SHALL BE BLENDED FOR SMOOTH CONTOUR BETWEEN PIPES.
4. GROUT CHANNEL TO SMOOTH FINISH.
5. FINISH BOTTOM TO EVEN SLOPE BROOM FINISH TO DRAIN TO CHANNEL.
6. LOCATE MANHOLE OPENING OPPOSITE OUTLET UNLESS OTHERWISE DIRECTED.

DRAWN AJD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL MANHOLE INVERT LAYOUT

SCALE NTS

DATE 12/10/21

APPR

STD DWG S-3D

01/14/2022 11:14:04 PM

MANHOLE PER STD
DWG S-3C, 60" MIN
DIAMETER

OUTSIDE
DROP
ASSEMBLY
SAME SIZE AS
MAIN


MAIN SIZE OVER 12"

CLASS "B" BACKFILL
COMPACTED IN 6" LIFTS BY
HAND TAMPERS FULL WIDTH
OF TRENCH TO UNDISTURBED
EARTH

6" OF BASEROCK
COMPACTED TO 95%

LONG SWEEP 90
DEGREE BEND

ENCASE 90° BEND IN
CONC 6" MIN DEPTH
ALL AROUND BASE



GENERAL NOTES:

1. OUTSIDE DROP MANHOLE FOR USE WITH MAIN SIZE OVER 12" ONLY

DRAWN	AJD
DIV	SANITARY
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STANDARD OUTSIDE DROP - LARGER THAN 12" PIPE



SCALE NTS

DATE 12/10/21

APPR


STD DWG S-4

01/14/2022 1:14:04 PM




NOTES:

1. INSIDE DROP MANHOLE FOR USE WITH MAIN SIZE 12" AND SMALLER ONLY

DRAWN AJD	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV SANITARY			DATE 12/10/21
REV DATE			APPR
		STANDARD INSIDE DROP - 12" PIPE AND SMALLER	STD DWG S-4A

01/14/2022 1:14:04 PM



NOTES:

1. TRACER WIRE SHALL BE EXTENDED WITHIN 18-INCHES OF FINISHED GRADE OR 6" BELOW LOWEST GRADE RING, WHICH EVER IS GREATER, TO A 1.75-INCH STAINLESS STEEL RUBBER CUSHIONED CLAMP MOUNTED TO MANHOLE WITH AS MIN 1/4" X 1-3/4" CONCRETE ANCHOR SCREW.

DRAWN AJD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


SCALE NTS

DATE 12/10/21

APPR

STD DWG S-5

3" & 4" PRESSURE SEWER LINE TERMINATION CLEANOUT



NOTES:

1. 2" COMBINATION AIR VALVE(SHORT VERSION) PER. 00445.11(I)(2)(d)
2. 2" STAINLESS STEEL BALL VALVE
3. 2" TEE OR 2" SADDLE TEE AS APPROVED FOR PRESSURE APPLICATIONS
4. 48" DIAMETER FLAT TOP MANHOLE.
5. 3/4"-1/2" WASHED GRAVEL
6. TRACER WIRE SHALL BE EXTENDED WITHIN 18-INCHES OF FINISHED GRADE OR 6" BELOW LOWEST GRADE RING, WHICH EVER IS GREATER, TO A 1.75-INCH STAINLESS STEEL RUBBER CUSHIONED CLAMP MOUNTED TO MANHOLE WITH AS MIN 1/4" X 1-3/4" CONCRETE ANCHOR SCREW.

DRAWN AJD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

AIR RELEASE/VAC BREAKER PRESSURE SEWER MH

SCALE NTS


DATE 12/10/21

APPR


STD DWG S-6


Preliminary

01/14/2022 1:14:04 PM



- NOTE: 6" OF BASEROCK COMPACTED TO 95%
1. ALL DUCTILE IRON FITTINGS THROUGH MANHOLE
 2. 48" MINIMUM DIAMETER MANHOLE
 3. TRACER WIRE SHALL BE EXTENDED WITHIN 18-INCHES OF FINISHED GRADE OR 6" BELOW LOWEST GRADE RING, WHICH EVER IS GREATER, TO A 1.75-INCH STAINLESS STEEL RUBBER CUSHIONED CLAMP MOUNTED TO MANHOLE WITH AS MIN 1/4" X 1-3/4" CONCRETE ANCHOR SCREW.

DRAWN AJD	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV SANITARY			DATE 12/10/21
REV DATE			APPR
		MAIN LINE CLEANOUT PRESSURE SEWER	STD DWG S-7



TYPICAL INSTALLATION IN TRAFFIC AREA

NOTE:

1. SHOWN WITH PLUG VALVE IN ENCLOSURE
2. 2" COMBINATION AIR VALVE (SHORT VERSION) PER. 00445.11(l)(2)(d)
3. 2" STAINLESS STEEL BALL VALVE
4. TRACER WIRE SHALL BE EXTENDED WITHIN 18-INCHES OF FINISHED GRADE OR 6" BELOW LOWEST GRADE RING, WHICHEVER IS GREATER, TO A 1.75-INCH STAINLESS STEEL RUBBER CUSHIONED CLAMP MOUNTED TO MANHOLE WITH AS MIN 1/4" X 1-3/4" CONCRETE ANCHOR SCREW.

DRAWN A.JD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PRESSURE SEWER SERVICE - TRAFFIC AREA



SCALE NTS

DATE 12/10/21

APPR


STD DWG S-8

01/14/2022 1:14:05 PM




NOTE:

1. 2x4 SERVICE MARKER TO FULL DEPTH OF TRENCH. PROJECT END 2FT MINIMUM ABOVE FINISH GRADE & PAINT GREEN ALL AROUND
2. SERVICE BOX COVER MARKED "SEWER"
3. CHECK VALVES 3" & LARGER APCO 100. 2" LEGEND T451
4. SERVICE BOX AND ALL APPARATUSES WITHIN ARE PRIVATELY OWNED BUT REQUIRED TO BE INSTALLED WITH PRESSURE SEWER SERVICE

DRAWN AJD DIV SANITARY REV DATE	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS DATE 12/10/21 APPR STD DWG S-9
		PRESSURE SEWER SERVICE - NON TRAFFIC AREA	

01/14/2022 1:14:05 PM



NOTES:

1. MULTIPLE SERVICE LINES SHALL CONNECT UPSTREAM AND OUTSIDE THE SAMPLE MANHOLE
2. SAMPLE MANHOLE TO BE LOCATED ON PRIVATE PROPERTY IN AN ACCESSIBLE AREA.
3. SAMPLING TEE OPTION IS ONLY PERMITTED WHEN APPROVED BY THE CITY ENGINEER AND ARE INTENDED FOR RETROFITS ON EXISTING SYSTEMS ONLY. CONSIDERED IN SITUATIONS WHERE EXISTING UTILITIES OR EASEMENTS PREVENT THE INSTALLATION OF MANHOLE.

DRAWN A.JD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SCALE NTS


DATE 12/10/21

APPR

STD DWG S-15

INDUSTRIAL AND COMMERCIAL SERVICES SAMPLING MH

01/14/2022 1:14:05 PM



1. ALL WORK DONE ON A VACUUM SEWER SHALL BE COORDINATED WITH PUBLIC WORKS 7 DAYS IN ADVANCE TO COORDINATE VACUUM STATION SHUT DOWN.
2. ALL JOINTS TO BE CONNECTED USING STANDARD PRIMER AND SOLVENT CEMENT. KEEP ALL JOINTS CLEAN AND FREE OF DEBRIS. JOINTS TO BE SCH40 DWV 220 OR APPROVED EQUAL.
3. AFTER INSTALLATION IS COMPLETE, OPEN DIVISION VALVE AND PERFORM VISUAL AND AUDIBLE INSPECTION OF EACH JOINT FOR LEAKS PRIOR TO TRENCH CLOSURE.
4. TRENCH BACKFILL TO BE IN ACCORDANCE TO S-1. MARKING TAPE AND TRACER WIRE TO BE INSTALLED ON ALL MAINS AND SERVICES.
5. INSTALL GRAVITY SEWER LATERALS IN CONFORMANCE WITH PLUMBING CODE. SERVICE LINE FROM THE PIT TO THE HOUSE IS OWNED AND MAINTAINED BY PROPERTY OWNER. CONNECTIONS TO THE AIRVAC VALVE PIT SHALL BE MADE AS PER MANUFACTURER'S SPECIFICATION.
6. AIR-INTAKE SHALL BE INSTALLED IN CONFORMANCE TO THE PLUMBING CODE AND SHALL BE PERMITTED WITH THE BUILDING DEPARTMENT UNDER A PLUMBING PERMIT.
7. PIT TO BE INSTALLED OUTSIDE OF SIDEWALK AND APRON SURFACES IN ROW OR CITY EASEMENT.
8. ALL WORK SHALL CONFORM TO AIR VAC SPECIFICATIONS. NO MORE THAN TWO SERVICES MAY CONNECT TO A ONE VACCUM PIT.
9. CONNECTION AVAILABILITY TO VALVE PIT TO BE DETERMINED BY THE CITY ENGINEER BASED ON MANUFACTURERS ALLOWABLE FLOW INTO PIT AND THE VACUUM SYSTEM.

DRAWN A.JD
DIV SANITARY
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

VACUUM SEWER SERVICE

SCALE NTS

DATE 12/10/21

APPR


STD DWG S-16

Preliminary

01/14/2022 1:14:05 PM


CITY OF BEND STANDARD DRAWINGS

Water (W)




NOTES:

1. REFER TO SPECIFICATION SECTION 01140.41 FOR APPROVED PUSH-ON AND MECHANICAL JOINT RESTRAINT SYSTEMS.
2. WOOD BLOCKING IS NOT PERMITTED IN THE BACKFILLED TRENCH.
3. INSTALL MARKING TAPE ON ALL MAINS AND SERVICES PER SPECIFICATION SECTION 01140.10 AND 01140.45.
4. WHEN INSTALLING A WATER LINE THAT CROSSES BELOW OR WITHIN 18 INCHES ABOVE A NON-POTABLE LINE, FOLLOW OAR 333-061-0050(9). ALL NON-POTABLE LINES SHALL BE TREATED AS "SEWER" LINES AS DESCRIBED IN OAR 333-061-0050(9).
5. COMPACTION SHALL MEET REQUIREMENTS OF SPECIFICATION SECTION 00405.46(c)

DRAWN AJD			CITY OF BEND		SCALE NTS
DIV WATER			STANDARD DRAWING		DATE 12/10/21
REV	DATE		710 NW WALL ST., BEND, OREGON 97701		APPR
			CITY OF BEND		STD DWG W-1
			WATER MAIN TYPICAL PROFILE		


01/14/2022 1:14:05 PM



TWO SERVICES SHARING ONE DITCH AT PROPERTY LINE

NOTE:

1. WATER METER BOXES SHALL BE LOCATED IN LANDSCAPE AREAS, NOT IN HARDSCAPE (I.E. SIDEWALKS & DRIVEWAYS). EXCEPTIONS REQUIRE APPROVAL OF CITY ENGINEER
2. SET WATER SERVICES A MINIMUM OF 10' FROM ALL SANITARY, FRANCHISE, STORM, AND ELECTRICAL SERVICES.
3. METER SHALL MATCH SERVICE LINE SIZE OR ONE SIZE SMALLER.
4. A 1" TAP NEAR A BELL SECTION SHALL BE SEPARATED FROM THE BELL BY A MINIMUM OF 2'. TAPS LARGER THAN 1" IN SIZE SHALL BE SEPARATED FROM THE BELL BY A MINIMUM OF 3'.
5. WHERE METERS ARE PLACED IN METER BANKS, A PERMANENT ADDRESS TAG PROVIDED BY THE CONTRACTOR SHALL BE PLACED ON THE METER BOX PRIOR TO 1 YEAR WARRANTY RELEASE.
6. IF AN EXISTING METER BOX, METER, OR HARDWARE WITHIN THE METER BOX DOES NOT MEET CURRENT CITY STANDARDS, CORRECTIONS OR REPAIRS SHALL BE MADE PRIOR TO THE METER BEING SET.
7. METER BOX SHALL BE SET ON 6" MIN CLASS B MATERIAL COMPACTED TO 95% OF MAXIMUM DENSITY.



DRAWN AJD

DIV WATER

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

RESIDENTIAL WATER SERVICE INSTALLATION

SCALE NTS


DATE 12/10/21

APPR


STD DWG W-4



1. RESIDENTIAL METER BOXES SHALL BE SET PARALLEL W/THE CURB LINE AND SHALL NOT BE INSTALLED WITHIN SIDEWALK OR PAVED AREAS
2. JUMPER SIZE 1" METER SETTER - 1 1/4"x11" SCHEDULE 80 THREADED NIPPLE (DOMESTIC) DRILLED TO PREVENT FLOW
3. METERS ARE TO BE THE SAME SIZE AS THE SERVICE LINE OR ONE SIZE SMALLER.
4. IF AN EXISTING BOX, METER, OR HARDWARE WITHIN THE METER BOX DOES NOT MEET CURRENT CITY STANDARDS, CORRECTIONS OR REPAIRS SHALL BE MADE TO THE EXISTING SERVICE TO MEET CURRENT CITY STANDARDS PRIOR TO THE METER BEING SET.
5. METER SHALL BE SET ON 6" MIN CLASS B MATERIAL COMPACTED TO 95% OF MAXIMUM DENSITY.

DRAWN AJD			CITY OF BEND		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701		SCALE NTS
DIV WATER							DATE 12/10/21
REV	DATE						APPR
			CITY OF BEND		3/4"-1" RESIDENTIAL METER SERVICE INSTALLATION		STD DWG W-4A

01/14/2022 1:14:05 PM



SECTION OFFSET METER "LOOP" WITH BACKFLOW PREVENTION ASSEMBLY

NOTES:

1. RESIDENTIAL METER BOXES SHALL BE SET PARALLEL W/THE CURB LINE AND SHALL NOT BE INSTALLED WITHIN SIDEWALK OR PAVED AREAS
2. JUMPER SIZE 1" METER SETTER - 1 1/4"x11" SCHEDULE 80 THREADED NIPPLE (DOMESTIC) DRILLED TO PREVENT FLOW
3. WHERE METER BOXES ARE INSTALLED IN A METER BANK, A BRASS OR STAINLESS STEEL TAG/PLAQUE SHALL BE MOUNTED TO THE INSIDE METER DOOR WITH THE LOT ADDRESS STAMPED PRIOR TO 1 YEAR WARRANTY RELEASE.
4. IF THE METER ASSEMBLY/BOX OR SERVICE LINE IS DAMAGED DURING CONSTRUCTION/SITE IMPROVEMENT ACTIVITIES, DURING THE WARRANTY PERIOD, OR IF THE EXISTING METER BOX OR SERVICE LINE DOES NOT MEET CURRENT CITY STANDARDS, THE DEVELOPER/PROPERTY OWNER SHALL UPGRADE THE COMPONENTS OF THE SERVICE THAT IS OUT OF CONFORMANCE.

DRAWN A.J.D.
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

3/4"-1" RESIDENTIAL METER SERVICE INSTALLATION


SCALE NTS

DATE 12/10/21

APPR

STD DWG W-4B

01/14/2022 1:14:05 PM



NOTES:

1. COMMERCIAL METER BOXES SHALL BE INSTALLED PERPENDICULAR TO THE CURB LINE WITH DOUBLE CHECK VALVE ASSEMBLY TO BE LOCATED ON PRIVATE PROPERTY.
2. WATER METER BOXES SHALL BE LOCATED IN LANDSCAPE AREAS WHEN POSSIBLE, SEE STD DWG W-5E FOR LOCATING METER BOX IN HARD SURFACE.
3. SET WATER SERVICES A MINIMUM OF 10' FROM ALL SANITARY, FRANCHISE, STORM, AND ELECTRICAL SERVICES. ALL TREE WELLS SHALL BE A MINIMUM 6 FEET FROM THE METER BOX INSTALLATION.
4. BACKFLOW PREVENTION DEVICES SHALL BE INSTALLED ON PRIVATE PROPERTY.
5. IF AN EXISTING METER BOX, METER, OR HARDWARE WITHIN THE METER BOX DOES NOT MEET CURRENT CITY STANDARDS, CORRECTIONS OR REPAIRS SHALL BE MADE TO THE EXISTING SERVICE TO MEET CURRENT CITY STANDARDS PRIOR TO THE METER BEING SET.
6. METER BOX SHALL BE SET ON 6" MIN CLASS B MATERIAL COMPACTED TO 95% OF MAXIMUM DENSITY.

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


COMMERCIAL & IRR METER SERVICE INSTALLATION

SCALE NTS

DATE 12/10/21

APPR

STD DWG W-5



TYPICAL 1" SERVICE WITH METER

NOTES:

1. COMMERCIAL METERS NOT TO BE LESS THAN 1-INCH. METER SIZE TO MATCH SERVICE LINE SIZE.
2. COMMERCIAL METER BOXES SHALL BE INSTALLED PERPENDICULAR TO THE CURB LINE WITH DOUBLE CHECK VALVE ASSEMBLY TO BE LOCATED ON PRIVATE PROPERTY PER STD DWG W-5.
3. COMMERCIAL METERS WILL NOT BE SET UNTIL BACKFLOW PREVENTION ASSEMBLY IS IN PLACE.
4. IF AN EXISTING METER BOX, METER, OR HARDWARE WITHIN THE METER BOX DOES NOT MEET CURRENT CITY STANDARDS, CORRECTIONS OR REPAIRS SHALL BE MADE TO THE EXISTING SERVICE TO MEET CURRENT CITY STANDARDS PRIOR TO THE METER BEING SET.
5. METER BOX SHALL BE SET ON 6" MIN CLASS B MATERIAL COMPACTED TO 95% OF MAXIMUM DENSITY.

DRAWN	AJD
DIV	WATER
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


1" COMMERCIAL & IRR METER SERVICE INSTALLATION

SCALE NTS

DATE 12/10/21

APPR

STD DWG W-5A



TYPICAL 2" SERVICE WITH 1-1/2" AND 2" METER



NOTES:

1. COMMERCIAL METERS WILL NOT BE SET UNTIL BACKFLOW PREVENTION ASSEMBLY IS IN PLACE
2. COMMERCIAL METER BOXES SHALL BE INSTALLED PERPENDICULAR TO THE CURB LINE WITH DOUBLE CHECK TO BE LOCATED ON PROPERTY
3. ALL METERS LESS THAN 2" WHEN USING A 2" SERVICE LINE ARE TO BE REDUCED WITHIN THE 2" METER SETTER
4. IF AN EXISTING METER BOX, METER, OR HARDWARE WITHIN THE METER BOX DOES NOT MEET CURRENT CITY STANDARDS CORRECTIONS OR REPAIRS SHALL BE MADE TO THE EXISTING SERVICE TO MEET CURRENT CITY STANDARDS PRIOR TO THE METER BEING SET.
5. DOUBLE CHECK ASSEMBLY SHALL BE INSTALLED USING THE UNIFORM BUILDING CODE (UBC) AND SHALL BE LOCATED ON A PRIVATE PROPERTY. THE ABOVE DIAGRAM IS FOR REFERENCE ONLY AND IS SUBJECT TO CHANGE BASED ON A REVIEW BY THE UBC PLANS EXAMINER.
6. METER BOX SHALL BE SET ON 6" MIN CLASS B MATERIAL COMPACTED TO 95% OF MAXIMUM DENSITY

DRAWN AJD	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701 1 1/2" & 2" COMMERCIAL AND IRRIGATION METER SERVICE INSTALLATION	SCALE NTS
DIV WATER			DATE 12/10/21
REV			APPR
DATE			STD DWG W-5B

STREET SIDE 14:05 PM

CUSTOMER SIDE



ITEM	QTY	DESCRIPTION
1	2EA	4"x3" FLG x FLG REDUCER & 3" FLG GATE VALVE WITH HANDWHEEL OR
2		4"x4" FLG GATE VALVE WITH HANDWHEEL
2	1	2" SE GATE VALVE AWWA C509
3	2	DOUBLE STRAP DR-25 SERVICE SADDLE, MUELLER OR APPROVED EQUAL
5	2	2" BRASS 90° COMP x COMP
6	2	2" TYPE K HARD COPPER PIPE
7	1	2" COMP UNION
8	1	OLD CASTLE 675-WA WITH OPENING FOR BILCO DOOR JD-3AL AND OSHA APPROVED LADDER (SEE STD DWG W-6)
9	1	WEEP HOLE (12"x12"x3" SUMP)
10	2	2" PIPE STAND "STANDON"
11	4	2" MPT x COMP ADAPTER
12	2	4"x3" REDUCER (WHERE 3" METER IS INSTALLED)

NOTES:

1. SEAL ALL OPENINGS IN VAULT WITH NON SHRINK GROUT
2. ENGINEER TO PROVIDE PIPE RESTRAINT DETAIL ENTERING & EXITING VAULT
3. METER SIZE TO MATCH SERVICE SIZE OR ONE SIZE SMALLER.
4. WHERE THE METER DOES NOT PROVIDE A TEST PORT, A 2" TEST PORT SHALL BE INSTALLED WITH 2" TAP SADDLE, 2" BRASS BALL VALVE, AND 2" BRASS NIPPLE.

DRAWN A.J.D.

DIV WATER

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

3" & 4" COMMERCIAL METER INSTALLATION



SCALE NTS

DATE 12/10/21

APPR

STD DWG W-5C

01/14/2022 1:14:05 PM



NOTES:

1. CONTRACTOR TO BRING ERT'S TO PUBLIC WORKS FOR INSTALLATION AND INSPECTION
2. ENGINEER TO PROVIDE PIPE RESTRAINT DETAIL ENTERING & EXITING VAULT
3. METER SIZE TO MATCH SERVICE SIZE OR ONE SIZE SMALLER.
4. WHERE THE METER DOES NOT PROVIDE A TEST PORT, A 2" TEST PORT SHALL BE INSTALLED WITH 2" TAPPING SADDLE, 2" BRASS BALL VALVE, AND 2" BRASS NIPPLE.

METER (INCH)	BYPASS (INCHES)	VAULT*	BILCO DOOR	A (INCHES)
6"	4"	810-LA	J-5AL	15"±
8"	6"	810-LA	JD-3AL	17"±
10"	8"	612-LA	JD-3AL	20"±
12"	12"	612-LA	JD-3AL	24"±

* VAULT SIZES MAY VARY BY ENGINEER DESIGN PROVIDE MIN DIMENSIONS ARE MAINTAINED

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

6" AND LARGER COMMERCIAL METER INSTALLATION

SCALE NTS


DATE 12/10/21

APPR

STD DWG W-5D

01/14/2022 1:14:06 PM

SIDEWALK INSTALLATION WITHIN 5' PUBLIC ACCESS EASEMENT AS REQUIRED BY BEND CENTRAL DISTRICT. MAY NOT BE APPLICABLE FOR ALL PROJECTS.



TREE WELL, MIN 4'X9' AS APPLICABLE. REFER TO 12.2.4.1 OF THE CONSTRUCTION DESIGN STANDARDS

TYPICAL INSTALLATION IN THE BEND CENTRAL DISTRICT OR WHERE WIDENED SIDEWALKS ARE REQUIRED BY DEVELOPMENT CODE. METERS TO BE PERMITTED WITHIN HARDSCAPE ONLY WHEN APPROVED BY THE CITY ENGINEER.

NOTE:

1. WATER METER BOXES SHALL BE LOCATED IN LANDSCAPE AREAS WHEN POSSIBLE. IF WATER METER BOX CAN BE LOCATED ON PRIVATE PROPERTY TO REMOVE IT FROM SIDEWALK, A UTILITY EASEMENT SHALL BE GRANTED TO THE CITY TO MAINTAIN THE METER.
2. AN EXPANSION JOINT IN THE SIDEWALK SHALL BE INSTALLED 12-INCH AROUND THE ENTIRE PERIMETER OF THE METER BOX.
3. STATE SPEC BASE ROCK SHALL BE COMPACTED TO 95% IMMEDIATELY BELOW AND FOR A MINIMUM OF 3 FEET AROUND THE METER BOX.
4. BACKFLOW DEVICE SHALL BE INSTALLED ON PRIVATE PROPERTY. WHERE BACKFLOW DEVICES CANNOT BE PLACED WITHIN LANDSCAPE, THE BOX SHALL BE INSTALLED OUTSIDE THE RIGHT OF WAY AND OUTSIDE A PUBLIC UTILITY EASEMENT. INSTALLATION OF BACKFLOW DEVICES WITHIN A BUILDING WILL BE GRANTED ON A CASE BY CASE BASIS BY THE CITY ENGINEER ONLY WHERE IT CAN BE ADEQUATELY SHOWN NOT TO FIT OUTSIDE THE BUILDING (EXAMPLE, THE BACKFLOW DEVICE, AND THEREFORE THE VAULT, IS TOO LARGE TO FIT)
5. SET WATER SERVICES A MINIMUM OF 10' FROM ALL SANITARY, FRANCHISE, STORM, AND ELECTRICAL SERVICES. ALL TREE WELLS SHALL BE A MINIMUM 6 FEET FROM THE METER BOX INSTALLATION.
6. WATER METERS SHALL NOT BE PLACED WITHIN VEHICULAR SURFACES (DRIVEWAYS) WITHOUT CITY ENGINEER APPROVAL.
7. COMMERCIAL WATER METER BOXES TO BE INSTALLED PERPENDICULAR TO THE CURB LINE, SEE STD DWG W-5. RESIDENTIAL WATER METER BOXES TO BE INSTALLED PARALLEL TO THE CURB LINE PER STD DWG W-4

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

METER INSTALLATION IN SIDEWALKS


SCALE NTS

DATE 12/10/21

APPR

STD DWG W-5E

01/14/2022 1:06 PM



SIDE VIEW

FRONT VIEW

NOTES:

1. GALVANIZED LADDER W/AN ALUMINUM EXTENSION BY OLDCASTLE (OR APPROVED EQUAL) (PER OAR 437, DIV 2, CODE OF FEDERAL REGULATIONS, TITLE 29, CHAPTER XVII PART 1910.27)
2. 5'-4" GALVANIZED LADDER FROM OLDCASTLE TO BE CUT DOWN TO 4'-7" BY CONTRACTOR FOR USE IN VAULT 675-WA. OLDCASTLE TO SUPPLY 49 1/2" ALUMINUM EXTENSION

DRAWN	AJD
DIV	WATER
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

GALV. LADDER W/ ALUM EXT FOR WATER VAULTS


SCALE NTS

DATE 12/10/21

APPR

STD DWG W-6

01/14/2022 1:14:06 PM



NOTES:

1. ALL PIPES SHALL HAVE RESTRAINED JOINTS.
2. MJ x MJ TEE OR MJxMJxSWIVEL (REQUIRES ENGINEER APPROVAL) WITH 6-INCH VALVE AT THE MAINLINE.
3. FINISH GRADE OF HYDRANT SHALL BE SET AT BURY LINE TO A MAXIMUM OF 3" BELOW BURY LINE FOR NEW INSTALLATION AND MAX OF 6" FOR RETROFITS. NO HYDRANT EXTENSIONS PERMITTED ON NEW INSTALLATIONS.
4. SET HYDRANT PLUMB. COMPACT ALL BACKFILL PER SPECIFICATIONS.
5. NON-WOVEN SEPARATION FILTER FABRIC OR PLASTIC (OSS TABLE 02320-4) INSTALLED BETWEEN UNDISTURBED EARTH AND DRAINROCK PRIOR TO BACKFILL.
6. HYDRANTS SHALL BE MANUFACTURER'S RED. NO OTHER COLOR IS PERMITTED.
7. BURY DEPTH IS MAX 6 FEET. USE 45 DEGREE OR 22.5 DEGREE BENDS TO ADJUST ACCORDINGLY.

DRAWN AJD

DIV WATER

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL HYDRANT

SCALE NTS

DATE 12/10/21


APPR

STD DWG W-7


Preliminary

01/14/2022 1:14:06 PM

PROPERTY TIGHT SIDEWALK;
FRONT OF SIDEWALK



**PROPERTY TIGHT SIDEWALK HYDRANT LOCATION AND CLEAR ZONE
PLAN VIEW**



**CURB TIGHT SIDEWALK HYDRANT LOCATION AND CLEAR ZONE
PLAN VIEW**

NOTES:

1. THE CLEAR ZONE PROHIBITS PARKING, FENCES, TREES, RETAINING WALLS, OR OTHER STRUCTURES THAT COULD INTERFERE WITH OPERATION OF HYDRANT. GRASS, MULCH, BARKDUST, AND GROUND COVER IS PERMITTED.
2. PROPERTY OWNERS SHOULD BE AWARE THAT GROUND COVER COULD BE DAMAGED WHEN THE HYDRANT IS USED OR WHEN HYDRANT MAINTENANCE IS PERFORMED.
3. CONCRETE PADS ARE TO BE A MINIMUM OF 6" THICK AND BE POURED AND PLACED ON 2" MIN. COMPACTED BASE ROCK PER SECTION OSS 00405.00
4. THERE SHALL BE A MINIMUM 4 FOOT CLEAR TRAVEL WIDTH ON SIDEWALKS ADJACENT TO HYDRANTS.
5. THE CURB SHALL BE PAINTED RED FOR A TOTAL OF 20 FEET, CENTERED ON THE HYDRANT.

DRAWN AJD

DIV WATER

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


HYDRANT LOCATION AND CLEAR ZONE

SCALE NTS

DATE 12/10/21

APPR

STD DWG W-8



A	B	C
COVER FROM CULVERT TO FINISH GRADE	CULVERT SIZE	SEPARATION CULVERT TO MAIN
12" OR LESS	6" THRU 12"	NOT LESS THAN 18"
12" OR MORE	6" THRU 12"	NOT LESS THAN 12"
12" OR LESS	14" THRU 24"	NOT LESS THAN 30"
12" OR MORE	14" THRU 24"	NOT LESS THAN 24"
	GREATER THAN 24"	NOT LESS THAN 36"

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SCALE NTS


DATE 12/10/21

APPR

STD DWG W-9


SEPARATION OF WATER LINE TO IRRIGATION CULVERTS

01/14/2022 1:14:06 PM



PROFILE VIEW

THE CONE SHALL BE VERTICALLY SEPARATED FROM THE WATER MAIN BY A MINIMUM OF 2 INCHES; NYLON POLYMER SAND BAGS TO BE PLACED BETWEEN THE CONE AND THE WATER MAIN FOR PROTECTION OF WATER MAIN



PLAN VIEW

BLOCKS TO BE PLACED BENEATH THE MANHOLE CONE; BLOCKS SHALL BE SEPARATED HORIZONTALLY FROM WATER MAIN BY A MINIMUM OF 4 INCHES

GENERAL NOTES:

- AIR RELEASE OR COMBINATION VALVES SHALL BE INSTALL AT ALL HIGH POINTS. WHERE THE HIGH POINT IS AT THE TOP OF A LONG ASCENT (1,250 FEET+) A COMBINATION AIR/VACUUM VALVE SHALL BE INSTALLED.
- 1" AIR RELEASE VALVE TO BE USED ON WATER MAINS LESS THAN 12" IN DIAMETER. 2" AIR RELEASE VALVE TO BE USED ON WATER MAINS GREATER THAN OR EQUAL TO 12" IN DIAMETER.

DRAWN A.JD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SCALE NTS


DATE 12/10/21

APPR


STD DWG W-10

1" & 2" STANDARD AIR RELEASE VALVE - TRAFFIC AREA

01/14/2022 1:14:06 PM



**AIR RELEASE VALVE LOCATION
PLAN VIEW**




GENERAL NOTES:

- AIR RELEASE OR COMBINATION VALVES SHALL BE INSTALL AT ALL HIGH POINTS. WHERE THE HIGH POINT IS AT THE TOP OF A LONG ASCENT (1,250 FEET+) A COMBINATION AIR/VACUUM VALVE SHALL BE INSTALLED.
- IF 1" AIR RELEASE VALVE IS INSTALLED IN TRAFFIC AREA, INSTALL PER STD DWG W-10.
- VAULT SHALL BE PRECAST VAULT WITH 2'X3' HATCH AND OPEN BOTTOM, OR APPROVED EQUAL.

DRAWN AJD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV WATER			DATE 12/10/21
REV			DATE
CITY OF BEND		1" STANDARD AIR RELEASE VALVE	APPR
			STD DWG W-10A


01/14/2022 1:14:06 PM



**AIR RELEASE VALVE LOCATION
PLAN VIEW**

STANDARD VALVE BOX
PER STD DWG W-30

ARI S050 AIR RELEASE VALVE OR
EQUAL W/INSULATION KIT



GENERAL NOTES:

1. AIR RELEASE OR COMBINATION VALVES SHALL BE INSTALL AT ALL HIGH POINTS. WHERE THE HIGH POINT IS AT THE TOP OF A LONG ASCENT (1,250 FEET+) A COMBINATION AIR/VACUUM VALVE SHALL BE INSTALLED.
2. SEE STD DWG W-10 FOR 2" AIR RELEASE VALVES LOCATED IN TRAFFIC AREAS.
3. VAULT SHALL BE ADVANCED PRECAST PRODUCT 233 VAULT WITH 2'X3' HATCH AND OPEN BOTTOM, OR APPROVED EQUAL.

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


2" STANDARD AIR RELEASE VALVE

SCALE NTS


DATE 12/10/21

APPR

STD DWG W-10B



TOP VIEW



SIDE VIEW

NOTES:

1. DOUBLE CHECK VALVE ASSEMBLIES (DCVAs) MAY BE INSTALLED VERTICAL AS WELL AS HORIZONTAL PROVIDED THAT THE ASSEMBLY IS APPROVED FOR VERTICAL INSTALLATIONS
2. DCVAs MAY BE INSTALLED BELOW GRADE IN A VAULT PROVIDED WATER TIGHT, THREADED PLUGS ARE INSTALLED IN THE TEST COCKS, BUT THE ASSEMBLY SHALL NOT BE SUBJECT TO CONTINUOUS IMMERSION
3. BLOWOUT PORTS, WHEN REQUIRED MUST BE INSTALLED DOWNSTREAM OF LAST ASSEMBLY SHUTOFF

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


TYPICAL DCVA INSTALLATIONS 2" AND SMALLER

SCALE NTS

DATE 12/10/21

APPR

STD DWG W-13



VAULT MODEL

PIPE SIZE	UTILITY VAULT OR EQUAL		BILCO DOOR OR EQUAL
	W/ FDC*	W/O FDC	
3		660-WA	J-5AL
4	676-WA	577-WA	J-5AL
6	687-WA	676-WA	J-5AL
8	5106-LA	687-WA	JD-3AL
10	5106-LA	5106-LA	JD-3AL

* FOR FIRE SPRINKLER VAULTS, REFER TO W-13B.
FIRE SPRINKLER VAULTS INSTALLED IN RIGHT
OF WAY OR UTILITY EASEMENT ONLY WHEN
APPROVED BY CITY ENGINEER.

NOTES:

- ENGINEER TO PROVIDE RESTRAIN DETAIL FOR ALL PIPE ENTERING & EXITING VAULT
- CONTRACTOR TO SEAL ALL OPENINGS IN VAULT WITH NON-SHRINK GROUT PRIOR TO BACKFILLING
- CONDUIT BROUGHT TO VAULT FOR PUMP POWER AND DETECTOR WIRING.
- ENGINEERED DESIGN TO BE PROVIDED WITH PERMIT.
- VAULT AND LID TO BE TRAFFIC RATED
- ALL FIRE LINES SHALL HAVE THE VAULT & DOUBLE CHECK DETECTOR ASSEMBLY (DCDA) INSTALLED CONCURRENTLY FOR TESTING & DISINFECTION TO THE CITY MAIN.
- PIPE SHALL MEET CITY ROW SPECIFICATIONS FROM MAIN TO DCDA

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

2" & LARGER DOUBLE CHECK VALVE ASSEMBLY

SCALE NTS


DATE 12/10/21

APPR

STD DWG W-13A

Preliminary

01/14/2022 1:14:06 PM



NOTES:

1. FIRE VAULT AND DCDA IS SHOWN FOR REFERENCE ONLY. VAULT AND PLUMBING BEYOND THE GATE VALVE SHALL BE INSTALLED PER PLUMBING CODE AND INSPECTED BY THE BUILDING DEPARTMENT.
 - 1.1. WHERE FIRE VAULT IS APPROVED BY CITY ENGINEER TO BE WITHIN THE ROW OR PUBLIC EASEMENT, VAULT SIZES ON STD DWG W-13A SHALL APPLY AND "FOR REFERENCE NOTES" ON THIS SHEET WOULD APPLY.
2. FIRE LINE TO BE 4" MIN DUCTILE IRON WATER MAIN PER CITY OF BEND SPECIFICATIONS. FIRE LINE TO BE SIZED BY ENGINEER UNDER A RIGHT OF WAY PERMIT.
3. VAULT TO BE SIZED BY ENGINEER IN CONFORMANCE TO BUILDING/FIRE/PLUMBING CODE, MEETING THE DOUBLE CHECK DETECTOR ASSEMBLY (DCDA) MANUFACTURER'S INSTALLATION SPECIFICATIONS.
 - 3.1. WHERE BUILDING IS WITHIN 20 FEET OF THE RIGHT OF WAY LINE, AND AS APPROVED BY THE BUILDING OFFICIAL, THE DCDA CAN BE WITHIN THE BUILDINGS MECHANICAL ROOM. ACCESS TO THE MECHANICAL ROOM TO BE PROVIDED BY AN EXTERIOR DOOR WITH KNOX BOX.
 - 3.2. VAULTS ARE TO BE PLACED OUT OF HARD SURFACES (SIDEWALKS, DRIVEWAYS/ROADWAYS, ECT.)
4. POST INDICATOR VALVE (PIV) AND FIRE DEPARTMENT CONNECTION (FDC) TO BE LOCATED IN CLEAR VIEW OF THE FRONTAGE STREET, WITH THE FDC LOCATED WITHIN AN ALLOWABLE DISTANCE FROM A HYDRANT. PIV AND FDC MAY BE MOUNTED ON THE BUILDING IN CONFORMANCE WITH THE FIRE CODE AND AS APPROVED. PIV AND FDC CAN BE MOUNTED OUTSIDE THE VAULT OR THROUGH THE VAULT LID PROVIDED THEY DON'T INTERFERE WITH VAULT ACCESS AND THE PENETRATIONS ARE GROUTED AND DON'T NEGATE THE STRUCTURAL INTEGRITY OF THE VAULT. PIV NOT TO BE USED IN-LIEU OF ISOLATION GATE VALVE AT PROPERTY LINE.
5. ALL ELECTRICAL TO VAULT AND PIV TO BE INSTALLED PER BUILDING AND FIRE CODE AS REQUIRED.
6. PIPE SHALL MEET CITY ROW SPECIFICATIONS FROM MAIN TO DCDA

DRAWN A.J.D.

DIV WATER

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

FIRE SPRINKLER LINE

SCALE NTS

DATE 12/10/21

APPR

STD DWG W-13B

01/14/2022 11:14:06 PM

DRAWING IS FOR REFERENCE ONLY

WHERE THE STRUCTURE IS PROPOSED
OUTSIDE THE RIGHT OF WAY OR
UTILITY EASEMENT

INSTALL TO
PLUMBING CODE

INSTALL TO CITY
STANDARDS

12" MIN - 60" MAX

PROPERTY LINE

12" MIN

DRAIN TO DAYLIGHT

LADDER
(SEE STD DWG W-6)

24" MIN

PLAN

EARTH BERM (OPTIONAL)

HATCH

PIPE STAND
SUPPORT
3" AND LARGER

90° BEND FLG

FINISH GRADE

RODENT SCREEN

12" MIN-24" MAX

DRAIN 1/4" PER FOOT
MIN SLOPE
BORE SIGHTED
TO DAYLIGHT

8" LEVELING COURSE
OF 3/4" CRUSHED ROCK

12" ABOVE FINISH GRADE
OR MAX FLOOD LEVEL

RETAINER
GLAND

90° BEND MJ MEGA-LUG
RETAINER GLANDS

SPOOL FLG x PE
(LENGTH VARIES)

PROFILE

NOTES:

1. THIS DRAWING IS FOR REFERENCE ONLY. INSTALL PER PLUMBING CODE AND BUILDING DEPARTMENT REQUIREMENTS.
2. ENGINEER TO PROVIDE RESTRAINT DETAIL FOR ALL PIPE ENTERING & EXITING VAULT
3. CONTRACTOR TO SEAL ALL OPENINGS IN VAULT WITH NON-SHRINK GROUT PRIOR TO BACKFILLING
4. HIGH OR LOW HAZARD CONNECTIONS SHALL BE IDENTIFIED AND VERIFIED WITH CITY CROSS CONNECTION SPECIALIST
5. PIPE SHALL MEET CITY ROW SPECIFICATIONS FROM MAIN TO DCDA

DRAWN AJD

DIV WATER

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SCALE NTS

DATE 12/10/21

APPR


STD DWG W-15

2 1/2"-10" REDUCED PRESSURE BACKFLOW ASSEMBLY

Don't forget to call 466-FPM

DRAWING IS FOR REFERENCE ONLY

WHERE THE STRUCTURE IS PROPOSED
OUTSIDE THE RIGHT OF WAY OR
UTILITY EASEMENT



PLAN

OREGON STATE APPROVED
PRESSURE BACKFLOW
PREVENTER

HATCH

SLOPE EARTH AWAY FROM
VAULT IN BERM AREA

12" MIN ABOVE
FINISH GRADE

UNION (TYP)

CURB

RODENT
SCREEN

FINISH GRADE

DRAIN TO DAYLIGHT

CONCRETE PAD
ON 6" OF BASE ROCK

ELEVATION

NOTES:

1. THIS DRAWING IS FOR REFERENCE ONLY. INSTALL PER PLUMBING CODE AND BUILDING DEPARTMENT REQUIREMENTS.
2. REDUCED PRESSURE BACKFLOW ASSEMBLY TO BE LOCATED DIRECTLY DOWN STREAM OF WATER METER
3. BRASS, STAINLESS, OR PLASTIC PLUGS TO BE INSTALLED IN TEST COCKS IF BELOW GROUND INSTALLATION
4. HIGH OR LOW HAZARD CONNECTIONS SHALL BE IDENTIFIED AND VERIFIED WITH CITY CROSS CONNECTION SPECIALIST

DRAWN AJD

DIV WATER

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

1"-2" REDUCED PRESSURE BACKFLOW ASSEMBLY

SCALE NTS

DATE 12/10/21

APPR


STD DWG W-15A

04/04/2022 1:14:37 PM

DRAWING IS FOR REFERENCE ONLY


WHERE THE STRUCTURE IS PROPOSED
OUTSIDE THE RIGHT OF WAY OR
UTILITY EASEMENT

(SEE NOTE 3)



PLAN

1060 ASSE
CLASS 1;
WATTS BOX,
SAFE-T-COVER,
HOT BOX, OR
EQUAL



PROFILE

NOTES:

1. THIS DRAWING IS FOR REFERENCE ONLY. INSTALL PER PLUMBING CODE AND BUILDING DEPARTMENT REQUIREMENTS OR AS BY MANUFACTURER'S REQUIREMENTS.
2. REDUCED PRESSURE BACKFLOW ASSEMBLY SHALL BE INSTALLED HORIZONTALLY UNLESS APPROVED FOR OTHER ORIENTATION
3. ALL CLEARANCES APPLY TO OUTSIDE, IN-BUILDING, AND VAULT INSTALLATIONS
4. STRUCTURE TO BE INSULATED AND HAVE A HEAT SOURCE TO KEEP ENCLOSURE AT 40°F (NFPA 13-4-5.4.1.1)
5. ENCLOSURE SHALL INCLUDE A BORE SIGHTED DRAIN TO DAYLIGHT CAPABLE OF DRAINING A FULL RELIEF VALVE DISCHARGE. MAKE/MODEL/SIZE WILL DICTATE THE SIZE OF THE ENCLOSURE.
6. ALL ASSEMBLIES 2 1/2" AND LARGER SHALL BE FLANGED
7. HIGH OR LOW HAZARD CONNECTIONS SHALL BE IDENTIFIED AND VERIFIED WITH CITY CROSS CONNECTION SPECIALIST

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


SCALE NTS

DATE 12/10/21

APPR

STD DWG W-15B


2 1/2" + REDUCED PRESSURE BACKFLOW ASSEMBLY



NOTES:

1. ALL MATERIAL SHALL BE SCHEDULE 40, GALVANIZED STEEL PIPE.
2. PROTECTIVE FINISH SHALL BE HOT-DIPPED, GALVANIZED GRAY.
3. CONTRACTOR TO INSTALL NO PARKING, FIRE LANE SIGN ON EACH SIDE OF GATE MEETING THE REQUIREMENTS OF OFC D103.6.
4. CONTRACTOR TO INSTALL TYPE III REFLECTIVE STRIPING ON BOTH SIDES OF GATE. STRIPING SHALL BE ALTERNATING RED/WHITE STRIPES, 6" WIDE AT 45 DEGREE ANGLE.
5. CONCRETE SHALL BE COMMERCIAL GRADE CONCRETE PER SPECIFICATION SECTION 00440.
6. GATE POSTS SHALL BE LOCATED OUTSIDE OF THE ROADWAY. IF PAVEMENT AND CURBS ARE PRESENT, GATE POSTS SHALL BE LOCATED BEHIND CURB.
7. COORDINATE INSTALLATION OF KNOX PADLOCK WITH CITY OF BEND FIRE DEPARTMENT.

DRAWN AJD			CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701		SCALE NTS
DIV WATER					DATE 12/10/21
REV	DATE		APPR		
			STD DWG W-21		
CITY OF BEND			FIRE GATE		



NOTES:

1. GATE VALVE, METER, REDUCED PRESSURE BACKFLOW ASSEMBLY & DOUBLE CHECK VALVE ASSEMBLY, & BOX WILL BE SUPPLIED & SET UP BY THE CITY WATER DEPT @ THE CONTRACTORS REQUEST AFTER OBTAINING A CITY HYDRANT PERMIT
2. HYDRANT PERMIT HOLDER TO PROTECT THE ENTIRE UNIT FROM FREEZING
3. BACKFLOW ASSEMBLY MUST BE TESTED IF UNIT IS MOVED TO ANOTHER LOCATION.

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


HYDRANT PERMIT/FILLING TANKER TRUCK

SCALE NTS

DATE 12/10/21


APPR


STD DWG W-22




NOTES:

1. USE CITY STANDARD VALVE BOXES, LIDS, AND 6" PVC EXTENSION.
2. BLOW-OFF UNIT SHALL BE BACKFILLED WITH 3/4" MINUS CRUSHED ROCK. ALL COMPACTION TO COMPLY WITH SPECIFICATION SECTION 00330.43 AND 00405.46(C).
3. TEMPORARY BLOW-OFF IS ONE REMOVED AT THE END OF WATER LINE TESTING AND INSTALLATION AND PRIOR TO PROJECT PAVING. A PERMANENT BLOW-OFF REMAINS ON THE PROJECT AFTER ACCEPTANCE.
4. PLACE BLOW-OFF STANDPIPE 3' INSIDE ROW LINE AT THE END OF STREET (2' FROM BARRICADE).
5. USE CITY STANDARD VALVE BOX, LID, AND 6" PVC EXTENSION FOR BLOW-OFF VALVE.
6. BLOW OFF RISER TO BE ONE CONTINUOUS PIECE.
7. USE EBAA IRON "MEGALUG" OR APPROVED EQUAL RETAINER GLAND ON MJ CAP. RESTRAIN PER ENGINEER.
8. 2" PVC PLUG WITH SQUARE NUT TO BE HAND TIGHTENED ONLY.


DRAWN AJD			CITY OF BEND	CITY OF BEND		SCALE NTS
DIV WATER				STANDARD DRAWING		DATE 12/10/21
REV	DATE			710 NW WALL ST., BEND, OREGON 97701		APPR
				STANDARD 2" BLOW-OFF ASSEMBLY		STD DWG W-23



1. USE CITY STANDARD VALVE BOXES, AND LIDS.
2. BLOW-OFF UNIT SHALL BE BACKFILLED WITH 3/4" MINUS CRUSHED ROCK. ALL COMPACTION TO COMPLY WITH SPECIFICATION SECTION 00330.43 AND 00405.46(C).
3. TEMPORARY BLOW-OFF IS ONE REMOVED AT THE END OF WATER LINE TESTING AND INSTALLATION AND PRIOR TO PROJECT PAVING. A PERMANENT BLOW-OFF REMAINS ON THE PROJECT AFTER ACCEPTANCE.
4. PLACE BLOW-OFF STANDPIPE 3' INSIDE ROW LINE AT THE END OF STREET (2' FROM BARRICADE).
5. USE CITY STANDARD VALVE BOX, LID, AND 6" PVC EXTENSION FOR BLOW-OFF VALVE.
6. BLOW OFF RISER TO BE ONE CONTINUOUS PIECE.
7. USE EBAA IRON "MEGALUG" OR APPROVED EQUAL RETAINER GLAND ON MJ CAP. RESTRAIN PER ENGINEER.

DRAWN AJD			CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701		SCALE NTS
DIV WATER					DATE 12/10/21
REV	DATE		APPR		
			STD DWG W-24		
		CITY OF BEND	4" BLOW-OFF DETAIL		

01/14/2022 1:14:07 PM



NOTES:

1. ALL PIPE AND STRUCTURES SHALL BE BACKFILLED WITH SCREENED MAX $\frac{3}{4}$ " MINUS CRUSHED ROCK. ALL COMPACTION TO COMPLY WITH SPECIFICATION SECTION 00330.43 AND 00405.46(C).
2. SET STATION AT LOT LINE UNLESS OTHERWISE SPECIFIED.
3. WHEN CROSSING, CATHODICALLY PROTECTED SYSTEM, INSTALL COPPER IN PVC SLEEVE FOR 5' EACH SIDE OF THE CROSSING.
4. WHERE NO SIDEWALK EXISTS, PLACE CONC. PAD AS SHOWN. WHERE SIDEWALKS EXIST, PLACE MIN. 12" AROUND BACK OF SAMPLE STA. AND INCORPORATE INTO NEW SIDEWALK POUR.

DRAWN AJD
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STANDARD WATER SAMPLING STATION


SCALE NTS

DATE 12/10/21


APPR

STD DWG W-25


01/14/2022 1:14:07 PM



OPTION 1: TESTING AND FLUSHING USING A BLOW OFF ASSEMBLY



OPTION 2: TESTING AND FLUSHING USING NEARBY HYDRANT



CONNECTION AFTER TESTING, FLUSHING AND APPROVAL

DRAWN A.J.D.
DIV WATER
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


CROSS CONNECTION DETAIL

SCALE NTS


DATE 12/10/21

APPR


STD DWG W-29



COVER PLAN




VALVE BOX EXTENSION SECTION



VALVE BOX ASSEMBLY DETAIL

NOTES:

1. VALVE BOX NOT TO REST ON OPERATING ASSEMBLY.
2. OPERATOR EXTENSION REQUIRED WHEN VALVE NUT IS DEEPER THAN 6' FROM FINISH GRADE.
3. CENTER VALVE BOX ON AXIS OF OPERATOR NUT.
4. VALVES TO BE INSTALLED WITH COMPACTED AGGR. BASE ON UNDISTURBED GROUND.
5. WELDS SHALL BE MINIMUM 0.5" ALL AROUND.
6. HOT DIP GALVANIZE OPERATOR EXTENSION AFTER FABRICATION.
7. CASTING SHALL MEET H2O LOAD REQUIREMENT.
8. PROVED 24"x24"x4" CONCRETE PAD WITH EXPANSION JOINT AROUND VALVE BOX WHEN INSTALLED OUTSIDE OF ROADWAY.
9. SEE PROJECT PLANS FOR DETAILS NOT SHOWN.
10. ALL VALVE BOXES SHALL BE PLACED OUTSIDE THE PATH OF TRAVEL ON SIDEWALK AND DRIVEWAY APRONS.

DRAWN AJD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV WATER			DATE 12/10/21
REV DATE			APPR
		VALVE BOX AND OPERATOR EXTENSION ASSEMBLY	STD DWG W-30


Preliminary

01/14/2022 1:14:07 PM

CITY OF BEND STANDARD DRAWINGS


Stormwater (STRM)

01/14/2022 1:14:07 PM



VEGETATED SWALE WITH OPTIONAL ROCK STORAGE RESERVOIR

NTS



SWALE OVERFLOW STRUCTURE

NTS

NOTES:

1. AMENDED TOPSOIL SHALL CONTAIN 20-30% TOPSOIL, 50-65% CLEAN SAND AND 5-20% COMPOST OR PEAT MOSS.
2. VOLUME AND DEPTH TO BE DETERMINED BY ENGINEER.
3. DRAIN ROCK AS REQUIRED FOR DRAINAGE CAPACITY. PEA GRAVEL TO BE USED TO PREVENT SOIL MIGRATION INTO DRAINAGE LAYER.
4. OPTIONAL ROCK RESERVOIR TO BE CONSTRUCTED WITH WASHED DRAIN ROCK WITH 40% VOIDS. NOT TO BE USED IN TREE WELLS.
5. AVOID COMPACTING SWALE AREA DURING CONSTRUCTION.
6. ADD HIGH POINT FLOW BYPASS TO AN APPROVED DISPOSAL POINT AS NECESSARY. OVERFLOW SHOULD PASS THROUGH A SEDIMENTATION MANHOLE OR PRE-TREATMENT PRIOR TO DISCHARGING TO A DRYWELL OR UIC.
7. AMENDED TOP SOIL CAN BE REPLACED WITH DRAIN ROCK FOR ROCK SWALES. ROCK SWALES CANNOT BE USED TO MEET PRETREATMENT REQUIREMENTS.
8. INSTALL CHECK DAMS AS REQUIRED AND PER DWG STRM-4.

DRAWN	AJD
DIV	STORM
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

VEGETATED SWALE DETAIL


SCALE NTS

DATE 12/10/21


APPR

STD DWG STRM-2

01/14/2022 1:14:07 PM



VEGETATED SWALE/ PLANTER
NTS



VEGETATED SWALE/ PLANTERS
W/ DRYWELL OVERFLOW
NTS

NOTES:

1. SWALE/SURFACE INFILTRATION FACILITIES NOT PERMITTED WITHIN PUES OR OVER FRANCHISE UTILITIES.
2. VOLUME AND DEPTH TO BE DETERMINED BY ENGINEER

DRAWN	AJD
DIV	STORM
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701



TYPICAL SWALE LAYOUT

SCALE NTS

DATE 12/10/21

APPR

STD DWG STRM-3



DRAWN AJD

DIV STORM

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

TYPICAL CURB CUT

SCALE NTS


DATE 12/10/21

APPR


STD DWG STRM-3A

01/14/2022 1:14:07 PM


18" MIN (NOTE 1)



CHANNEL CROSS SECTION



CHECK DAM PROFILE



SPACING BETWEEN CHECK DAMS

NOTES:

1. KEY STONE INTO THE CHANNEL BANKS AND EXTEND DAM A MINIMUM OF 18" TO PREVENT FLOW AROUND DAM.
2. L IS EQUAL TO THE DISTANCE SUCH THAT 'POINT A' AND 'POINT B' ARE OF EQUAL ELEVATION.
3. CHECK DAMS SHALL BE INSTALLED PER CENTRAL OREGON STORMWATER MANUAL (COSM) REQUIREMENTS.

DRAWN LJC

DIV STORM

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

CHECK DAM DETAIL


SCALE NTS

DATE 12/1/17

APPR


STD DWG STRM-4

01/14/2022 1:14:08 PM



INFILTRATION PLANTER TYPICAL SECTION

NTS



FLOW-THROUGH PLANTER TYPICAL SECTION

NTS

NOTE:

1. NOT FOR USE ALONG STREETS WITH POSTED SPEED ABOVE 25 MPH, UNLESS OUTSIDE THE CLEAR ZONE.
2. AMENDED TOPSOIL PER SPECIFICATION 01040
3. VOLUME AND DEPTH TO BE DETERMINED BY ENGINEER.
4. USE INFILTRATION PLANTER IF EXISTING SITE HAS AN INFILTRATION RATES > 0.5 IN/HR.
5. PLACE OVERFLOW PIPE 2" BELOW TOP OF PLANTER.
6. TO AVOID UIC REGULATION DO NOT USE PERFORATED PIPE OUTSIDE OF THE FLOW-THROUGH PLANTER OR WITH THE INFILTRATION PLANTER.

DRAWN AJD
DIV STORM
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


STORMWATER PLANTER DETAIL

SCALE NTS

DATE 12/10/21


APPR

STD DWG STRM-5



PLAN VIEW

NTS



NOTES:

1. MIN. FILTER STRIP LENGTH IS; 4' FOR A 10' FLOW PATH, 4.5' FOR A 25' FLOWPATH AND 5.5' FOR A 30' FLOWPATH
2. AMENDED TOPSOIL PER SPECIFICATION 01040
3. FLOW SPREADER IS OPTIONAL. IF USED THE GRAVEL MUST BE WIDER THAN DEEP TO AVOID UIC REGULATIONS.

SECTION A-A

NTS

DRAWN AJD
DIV STORM
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STORMWATER FILTER DETAIL


SCALE NTS

DATE 12/10/21

APPR

STD DWG STRM-6

01/14/2022 1:14:08 PM



NOTES:

1. ALL PRE-CAST SECTIONS SHALL CONFORM TO REQUIREMENTS OF ASTM C-478.
2. AWWA C900 PIPE SHALL BE USED WITHIN TRAVEL AREAS. ASTM D3034 PIPE WHERE STORM PIPE WILL BE INSTALLED PER SANITARY SEWER REQUIREMENTS OR OUTSIDE OF TRAVEL AREAS.
3. MANHOLES SHALL BE PLACED OUTSIDE SIDEWALK, APRONS & STREET SURFACES UNLESS APPROVED BY THE CITY ENGINEER.
4. A 3 POINT MECHANICAL ADJUSTMENT SYSTEM SUCH AS RAD'S OR APPROVED EQUAL SHALL BE USED TO ADJUST MANHOLE FRAME AND COVER TO FINISH GRADE.
5. SUMP SIZE TO BE DESIGNED IN ACCORDANCE WITH COSM - 20 CF OF SUMP VOLUME FOR EACH 1.0 CFS DESIGN FLOW - NOT LESS THAN 48" DEPTH.
6. MANHOLES WITH MORE THAN 3 CONNECTIONS, OR PIPES 12" OR LARGER TO BE 60" MANHOLES
7. OIL/WATER SEPARATOR SNOUT BMP 24R, OR APPROVED EQUAL. SECURE TO MANHOLE WITH FIVE (5) 5/8"x1-12" STAINLESS STEEL RED HEAD BOLTS, WASHERS AND NUTS, OR AS APPROVED BY MANUFACTURER.

DRAWN A.JD
DIV STORM
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


STORMWATER SEDIMENTATION MANHOLE

SCALE NTS

DATE 12/10/21


APPR

STD DWG STRM-7



SECTION A-A

NTS




SECTION B-B



NTS

THIS SEDIMENTATION MANHOLE OPTION IS USED WHEN A CATCH BASIN OR INLET ARE PROPOSED AND A CONFLICT EXISTS PREVENTING INSTALLATION OF THE STANDARD SEDIMENTATION MANHOLE (STRM-7).

NOTES:


- ALL REINFORCEMENT TO BE PLACED A MINIMUM OF 2" CLEAR OF NEAREST FACE OF CONCRETE UNLESS OTHERWISE SHOWN OR NOTED.
- ALL PRECAST PRODUCTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM C478.
- ALL CONCRETE SHALL BE COMMERCIAL GRADE CONCRETE.
- INLET TOP MAY BE CAST-IN-PLACE OR PRECAST. ALL PRECAST INLETS SHALL CONFORM TO REQUIREMENTS OF ASTM C913.
- VARY ANCHOR BOLT LENGTH AND REINFORCING BAR PLACEMENT AS REQUIRED BY CURB EXPOSURE E.
- SEE COB STD DWG R-3 FOR CURB DETAILS.
- SEE ODOT STD DWG RD356 FOR MANHOLE ADJUSTMENT RING. SEE COB STD DWG STRM-8 FOR CAST IRON MANHOLE ADJUSTMENT RING AND COVER.
- SUMP SIZE TO BE DESIGNED IN ACCORDANCE WITH COSM - 20 CF OF SUMP VOLUME FOR EACH 1.0 CFS DESIGN FLOW - NOT LESS THAN 48" DEPTH.

DRAWN A.JD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV STORM			DATE 12/10/2021
REV DATE			APPR
			STD DWG STRM-7A
CITY OF BEND		STORMWATER SEDIMENTATION MANHOLE - ALTERNATE	



STORMWATER MANHOLE LID DETAIL

NTS



NOTE:

1. MANHOLE LID ONLY TO BE USED ON CITY OF BEND PUBLIC DRYWELLS AND SEDIMENTATION MANHOLES. PRIVATELY OWNED DRYWELLS AND SEDIMENT MANHOLES SHALL NOT USE A CITY OF BEND MANHOLE LID.
2. HINGED MANHOLE LIDS ARE NOT PERMITTED UNLESS OTHERWISE APPROVED BY THE CITY ENGINEER.
3. ALL MANHOLE LIDS SHALL BE PLACED OUTSIDE THE PATH OF TRAVEL OF SIDEWALKS AND DRIVEWAY APRONS.

DRAWN	AJD
DIV	STORM
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701




STORMWATER MANHOLE LID DETAIL

SCALE NTS

DATE 12/10/21


APPR

STD DWG STRM-8



NOTES:

1. REMOVE SUFFICIENT CURB TO POUR BACK WALL. TOP SECTION MAY BE POURED MONOLITHIC WITH SIDEWALK.
2. CURB INLETS TO BE USED ON ARTERIAL AND COLLECTOR ROADWAYS.
3. "E" = CURB EXPOSURE.



KEYWAY DETAIL

DRAWN A.J.D.
DIV STORM
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STANDARD CATCH BASIN SPECIAL INLETS


SCALE NTS

DATE 12/10/21

APPR

STD DWG STRM-9

01/14/2022 1:14:08 PM



NOTES:

* SEE ALSO THE CITY OF BEND STANDARDS AND SPECIFICATIONS FOR DESIGN CRITERIA

- 6" CONCRETE CAP, CL. 3000, EXTEND TO UNDISTURBED MATERIAL 2' MIN. REQUIRED WITHIN ALL CITY OF BEND RIGHT OF WAY UNLESS NOTED OTHERWISE.
- MOISTURE BARRIER-2 LAYERS OF 4 MIL POLY. ON ALL ROCK INSTALLATIONS.
- NONWOVEN GEOFABRIC CONFORMING TO DRAINAGE GEOTEXTILE, OREGON TABLE 02320-1 REQUIRED ON ALL EARTH OR GRAVEL EXCAVATIONS TO 24" INTO ROCK. LAP 24" WITH MOISTURE BARRIER.
- LINE INSIDE OF PERFORATED BARREL WITH HEAVY WEIGHT VINYL SCREEN, SUCH AS FULL FLOW VINYL SCREEN THAT MEETS THE REQUIREMENTS OF SPECIFICATION SECTION 00470. LINER SHALL BE FULLY AND CONTINUOUSLY ANCHORED, TOP AND BOTTOM OF EACH SECTION. ATTACH BY OVERLAPPING 12" MIN. BETWEEN JOINT OF MANHOLE CONE AND PERFORATED BARREL SECTION. INLET PIPE SHALL BE EXTENDED THROUGH THE SCREEN IF SCREEN IS ATTACHED ABOVE THE PIPE.
- PRE-CAST SECTIONS SHALL CONFORM TO THE REQUIREMENTS OF ASTM C-478. ALL CONCRETE SHALL BE COMMERCIAL GRADE CONCRETE
- STANDARD RING AND COVER REQUIRED IN RIGHT-OF-WAY AREAS. NO SLOTTED COVERS WILL BE ALLOWED IN LIEU OF A CATCH BASIN.
- CLASS "A" BACKFILL COMPACTED TO 95.0% OPTIMUM DRY DENSITY (AASHTO T-99).
- CLASS "B" BACKFILL COMPACTED TO 95.0% OPTIMUM DRY DENSITY (AASHTO T-99).
- PERFORATIONS TO BE 60" BELOW EXISTING UNDISTURBED GROUND.
- INLET PIPE MUST BE DESIGNED SO IT CAN BE PLUGGED IN CASE OF SPILL. ALL PIPE PENETRATIONS ARE TO BE GROUTED OR WATER-TIGHT SEALED. PIPE INLETS NOT TO ENTER DRYWELL WITH PERFORATED BARREL.
- DRYWELL RIMS TO BE PLACED OUTSIDE OF SIDEWALK, APRON & STREET SURFACES UNLESS APPROVED BY THE CITY ENGINEER.
- PLANS SHALL PROVIDE VOLUME AND AREA OF ROCK PLACEMENT. ROCK PLACEMENT SHALL BE OUTSIDE WATER/SEWER TRENCHES. WHERE ROCK ENTERS PRIVATE PROPERTY, A DRAINAGE EASEMENT SHALL BE RECORDED.
- GEOFABRIC TO BE EXTENDED FROM THE CONCRETE CAP TO BOTTOM OF DRYWELL STRUCTURE. WHERE THE EXCAVATION IS WITHIN SOLID ROCK (NO SIDEWALL SLOUGHING), GEOFABRIC CAN BE WAIVED AT ENGINEER'S DISCRETION

DRAWN AJD

DIV STORM

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STANDARD PRE-CAST DRYWELL



SCALE NTS

DATE 12/10/21

APPR

STD DWG STRM-10

01/14/2022 1:14:08 PM



NOTES:

1. CROSS PIPE ELEV MAY REQUIRE OTHER UTILITIES (SEWER, WATER, ETC) TO BE LOWERED TO PROVIDE MINIMUM SEPARATIONS
2. ALL PIPE PENETRATIONS ARE TO BE GROUTED OR WATER TIGHT SEALED.
3. DRYWELL AND TREATMENT FACILITY NOT TO BE PLACED IN DRIVEWAY OR SIDEWALK UNLESS APPROVED BY THE CITY ENGINEER.
4. WHEN DRY UTILITIES WILL BE INSTALLED BETWEEN STRUCTURES, PROVIDE MINIMUM 5' SEPARATION.

DRAWN **AJD**
DIV **STORM**
REV DATE



CITY OF BEND

CITY OF BEND STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701



DRYWELL W/ MANUFACTURED TREATMENT LAYOUT

SCALE **NTS**

DATE **12/10/21**

APPR

STD DWG **STRM-11**



NOTES:

1. UNLESS OTHERWISE SPECIFIED, ALL CATCH BASINS TO BE DOUBLE CATCH BASIN
2. BACKFILL TO BE COMPACTED TO 95% OF OPTIMUM PER SPECIFICATION SECTION 00330.43
3. CROSS PIPE ELEV MAY REQUIRE OTHER UTILITIES (SEWER, WATER, ETC) TO BE LOWERED TO PROVIDE MINIMUM SEPARATIONS
4. ALL PIPE CONNECTIONS TO BE GROUTED PER SPECIFICATION SECTION 00470.40
5. CONTRACTOR IS RESPONSIBLE TO KEEP CATCH BASIN CLEAN AND FREE OF SEDIMENT DURING CONSTRUCTION
6. CONTRACTOR IS RESPONSIBLE TO COVER AND BARRICADE ALL CATCH BASINS UNTIL GRATE IS INSTALLED
7. STANDARD CATCH BASINS ARE LIMITED TO LOCAL STREETS AND SHALL NOT BE USED ON ARTERIAL & COLLECTOR ROADWAYS. CURB INLETS ARE TO BE USED ON ARTERIAL & COLLECTOR ROADWAYS.
8. SEE DRG R-11 FOR PAVEMENT RESURFACING

DRAWN AJD
DIV STORM
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STANDARD CATCH BASIN

SCALE NTS


DATE 12/10/21

APPR


STD DWG STRM-12

Preliminary

01/14/2022 1:14:08 PM



STEEL FRAME



DUCTILE IRON GRATE

DRAWN AJD
DIV STORM
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STORMWATER GRATE


SCALE NTS

DATE 12/10/21


APPR

STD DWG STRM-13A

01/14/2022 1:14:08 PM




CAST IRON COMBINATION CATCH BASIN INLET




NOTES:

1. SEE NOTES ON STD DWG STRM-12
2. COMBINATION CATCH BASIN INLET TO BE USED ON COLLECTOR AND LOCAL STREETS WHEN THE ROAD GRADE EXCEED 6%

DRAWN AJD			CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701		SCALE NTS
DIV STORM					DATE 12/10/21
REV	DATE		APPR		
			STD DWG STRM-13B		
CITY OF BEND			COMBINATION CATCH BASIN INLET		


01/15/2022 1:14:08 PM

NOTE: TAPER LENGTHS SHALL BE UTILIZED FOR ASPHALT PAVEMENT OVERLAY PROJECTS. ADJUST GRIND AS REQUIRED.



SECTION VIEW

SCALE:
HORIZONTAL: 1"=5'
VERTICAL: 1"=1'



PLAN VIEW

SCALE:
HORIZONTAL: 1"=5'

DRAWN	LJC
DIV	STORM
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

EXISTING CATCH BASIN PAVEMENT RESURFACING

SCALE NTS


DATE 3/31/19

APPR

STD DWG STRM-14

Preliminary

01/14/2022 1:14:05 PM



EXTENDED DETENTION DRY POND (PLAN VIEW)

NTS

NOTE:

THE WATER QUALITY TREATMENT STORM SHOULD DRAIN WITHIN 48 HOURS. IF ADDITIONAL STORAGE IS INCLUDED IN THE POND FOR LARGER STORM EVENTS, THE TOTAL FACILITY SHOULD DRAIN WITHIN 72 HOURS FOLLOWING THE PEAK DESIGN STORM EVENT.

DRAWN CJH

DIV STORM

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

INFILTRATION POND DETAIL


SCALE NTS

DATE 1/2021

APPR

STD DWG STRM-16

01/14/2022 1:14:09 PM



PART NO.	DESCRIPTION
1	STRAIGHT PLUG
2	BOTTOM HINGE
3	TOP HINGE
4	CORNER ELBOW
5	PLUNGER ROD
6	LATCH FORK
7	FORK CATCH
8	PLUNGER ROD CATCH
9	LOCK KEEPER GUIDE
10	LOCK KEEPER W/ CITY LOCK
11	ORNAMENTAL TOPS
12	TRUSS RODS
13	STRETCHER BAR
14	HOOK BOLTS

GATE FRAME MEMBERS SIZE & WEIGHT		
GATE LEAF WIDTH OF 6 FT OR LESS	OUTSIDE DIMENSIONS INCHES	WEIGHT LBS/FT
ROUND	1.66	2.27
*ROUND	1.66	1.84
* GRADE B HIGH STRENGTH STEEL		

GATE POST SIZE AND WEIGHT		
GATE LEAF WIDTH OF 6 FT OR LESS	OUTSIDE DIMENSIONS INCHES	WEIGHT LBS/FT
ROUND	2.875	5.79
*ROUND	2.875	4.64
* GRADE B HIGH STRENGTH STEEL		

SHAPE, SIZE AND WEIGHT REQUIREMENTS FOR FENCE POSTS AND RAILS			
ITEM	SHAPE	OUTSIDE DIMENSIONS INCHES	WEIGHT LBS/FT.
**			
TERMINAL POST	ROUND	2.375	3.65
LINE POSTS	*ROUND	2.375	3.12
TOP & BRACE RAILS	ROUND	1.90	2.72
	*ROUND	1.90	2.28
	ROUND	1.66	2.27
	*ROUND	1.66	1.84
* GRADE B HIGH STRENGTH STEEL			
** INCLUDES END, CORNER, ANGLE, INTERSECTION AND INTERMEDIATE BRACED POSTS			

DRAWN A.J.D.
DIV STORM
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

CHAINLINK FENCE DETAIL

SCALE NTS


DATE 12/10/21

APPR

STD DWG STRM-17

Preliminary

01/14/2022 1:14:09 PM



NOTES:

1. WEEP HOLE INSTALLATION WILL ONLY BE PERMITTED WHERE APPROVED DURING LAND USE AND WHERE THE RIGHT OF WAY STORM SYSTEM WAS SIZED FOR THE ADDITIONAL STORMWATER RUNOFF.
2. ALL STORM PIPE IS OWNED AND MAINTAINED BY THE HOMEOWNER. THE SYSTEM MUST BE CLEANED AND REPAIRED AS NEEDED TO KEEP THE SYSTEM FUNCTIONAL. ONLY ROOF RUNOFF AND HARD SURFACE RUNOFF CAN BE CONNECTED INTO THE WEEP HOLE PIPE TO REDUCE SEDIMENTS AND DEBRIS FROM CLOGGING THE PIPE AND CURB LINE.
3. SEPARATION: WEEP HOLES ARE NOT PERMITTED WITHIN 4 FEET OF OTHER WEEP HOLE PENETRATION, 2 FEET FROM TOP OF DRIVEWAY, OR 2 FEET OF ANY WATER OR SEWER LATERAL. PIPE MUST BE A MINIMUM 12" FROM ANY METER BOX. WEEP HOLES AND PIPING WILL NOT BE PERMITTED WITH CURB TIGHT SIDEWALKS
4. WEEP HOLES WILL NOT BE PERMITTED ON ARTERIAL AND COLLECTOR ROADWAYS.
5. THE STORM PIPE WILL NOT BE PERMITTED WITHIN THE CONCRETE SIDEWALK. A MINIMUM 1-INCH OF AGGREGATE OVER THE PIPE AND A LAYER OF VISQUEEN BARRIER PLACED BETWEEN THE PIPE AND CONCRETE. THIS IS TO ALLOW THE SIDEWALK PANEL TO REMOVED AS NEEDED WITHOUT BRINGING THE PIPE WITH IT. THE VISQUEEN BARRIER WILL BE CUT AT OR JUST BEFORE THE EDGE OF THE SIDEWALK AND NOT EXTENDED INTO THE LANDSCAPE STRIP.
6. SIDEWALK CANNOT BE BONDED FOR WHEN WEEP HOLE AND STORM PIPE INSTALLATIONS ARE PROPOSED UNLESS OTHERWISE APPROVED BY THE CITY ENGINEER.
7. ALL WEEP HOLE STORM PIPE WITHIN THE RIGHT OF WAY MUST BE 3-INCH SCHEDULE 40 PVC.
8. STORM PIPES MUST BE EXTENDED TO THE RIGHT OF WAY OR TO THE BACK OF ANY PUE, WHERE APPLICABLE

DRAWN AJD

DIV STORM

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

CURB WEEP HOLE DETAIL

SCALE NTS

DATE 12/10/21

APPR

STD DWG STRM-18


Preliminary

01/14/2022 1:14:09 PM


CITY OF BEND STANDARD DRAWINGS

Erosion (E)


01/14/2022 1:14:05 PM



FRONT VIEW




PROFILE VIEW




PLAN VIEW

CONNECT JOINTS WITH TURNED END OR POST SPACING OVERLAP CONNECTION (SEE DETAILS AND NOTE 2)



TURNED END CONNECTION



POST SPACING OVERLAP CONNECTION

NOTES:

1. FABRIC WITHOUT SEWN-IN SLEEVES IS NOT RECOMMENDED. IF USED, INSTALL FENCE POSTS PER MANUFACTURER RECOMMENDATIONS.
2. THE GEOTEXTILE FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, GEOTEXTILE SHALL BE SPLICED TOGETHER AT A SUPPORT POST UTILIZING A TURNED END OR POST SPACING OVERLAP CONNECTION.
3. THE FENCE POSTS SHALL BE SPACED A MAXIMUM OF 6 FEET APART AND INSTALLED INTO THE GROUND 18 INCHES MIN. FENCE POSTS SHALL BE 2" X 2" FIR, PINE, OR STEEL. THE GEOTEXTILE FABRIC FENCE SHALL BE INSTALLED TO FOLLOW THE SLOPE CONTOURS, TO MAXIMIZE PONDING EFFICIENCY WHERE FEASIBLE.
4. BURY BOTTOM OF THE GEOTEXTILE FABRIC 6 INCHES BELOW GRADE. BACKFILL AND COMPACT.
5. POSTS SHALL BE INSTALLED WITHIN THE SLEEVE ON THE UPHILL SIDE GEOTEXTILE FABRIC.
6. GEOTEXTILE FABRIC FENCE SHALL BE REMOVED WHEN IT HAS SERVED ITS USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY PROTECTED AND STABILIZED.
7. GEOTEXTILE FABRIC FENCES SHALL BE INSPECTED BY APPLICANT/CONTRACTOR AFTER EACH RAIN OR SNOW EVENT AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
8. MAXIMUM RECOMMENDED FENCE WIDTH IS 500 FEET. MAXIMUM TRIBUTARY AREA IS 0.25 ACRE PER 100' OF FENCE. MAXIMUM RECOMMENDED SLOPE LENGTH IS 100'.

DRAWN A.J.D.
DIV EROSION
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SEDIMENT FENCE DETAIL


SCALE NTS

DATE 12/10/21

APPR


STD DWG E-1

01/14/2022 1:14:09 PM



PLAN VIEW

DITCH INLET



CURB INLET BIO-BAG INLET PROTECTION

NOTES:

1. ADDITIONAL MEASURES MUST BE CONSIDERED DEPENDING ON SOIL TYPES.
2. BIO-BAGS SHOULD BE STAKED WHERE APPLICABLE USING (2) 1"X2"X3' WOOD STAKES OR APPROVED EQUAL.
3. BIO-FILTER BAGS MUST BE REMOVED AND HAULED OFF-SITE FOR DISPOSAL BY THE CONTRACTOR UPON PROJECT STABILIZATION.
4. BIO-FILTER BAGS MAY BE USED SHORT TERM WITH UTILITY WORK AND WITH PHASING OF DEVELOPMENT.
5. APPROVED EQUAL SHALL BE USED ON ROADS WITH BIKE LANES
6. SEDIMENT BARRIERS SHALL BE MAINTAINED UNTIL UPHILL AREA IS PERMANENTLY STABILIZED.
7. AT NO TIME SHALL MORE THAN 2-INCHES OF SEDIMENT BE ALLOWED TO ACCUMULATE BEHIND BIO-FILTER BAGS.
8. NEW SEDIMENT BARRIERS SHALL BE INSTALLED AS REQUIRED TO CONTROL SEDIMENT TRANSPORT.

DRAWN A.JD
DIV EROSION
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


BIO-FILTER BAG INLET PROTECTION

SCALE NTS

DATE 12/10/21

APPR

STD DWG E-2A



NOTES:

1. INSTALL PRE-FABRICATED FILTER INSERTS ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
2. FIELD FABRICATED INSERTS ARE NOT PERMITTED.
3. PRE-FABRICATED INSERTS WITH PROVISIONS FOR OVERFLOW ARE ONLY ALLOWED WHEN ACCOMPANIED BY ADDITIONAL BMP TO PREVENT THE POTENTIAL OF SEDIMENTS ENTERING PROJECT STORM SYSTEMS.

DRAWN	LJC
DIV	EROSION
REV	DATE
	12/1/17



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


FILTER INSERT INLET PROTECTION

SCALE NTS

DATE 12/1/17

APPR

STD DWG E-2B



NOTE:

1. USE WOOD OR METAL FENCE POSTS. POST SPACING & DEPTH SHALL BE INSTALLED TO ADEQUATELY SUPPORT THE FENCE IN AN UPRIGHT MANNER.
2. MAXIMUM FENCE OPENINGS SHALL BE 2"X2".

DRAWN LJC	
DIV EROSION	
REV	DATE
	12/1/17



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


TREE/VEGETATION PROTECTION FENCING

SCALE NTS


DATE 12/1/17

APPR


STD DWG E-3



SLOPE APPLICATION - PERSPECTIVE VIEW



STAKING DETAIL



SLOPE APPLICATION - PLAN VIEW

DRAWN A.JD
DIV EROSION
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

STRAW WATTLE


SCALE NTS

DATE 12/10/21


APPR

STD DWG E-4

01/14/2022 11:45 AM




STOCKPILE STABILIZATION
NTS



ISOMETRIC VIEW
NTS

STAPLES
NTS



TOP BERM
NTS

NOTES:

1. PRIOR TO A SITE'S FINAL APPROVAL, ALL DISTURBED STEEP SLOPES MUST BE TREATED FOR LONG-TERM EROSION CONTROL. DISTURBED GROUND OF LESSER SLOPES SHALL BE TREATED FOR EROSION CONTROL IF SEDIMENTS HAS THE POTENTIAL TO LEAVE THE SITE.
2. MATS/BLANKETS SHOULD BE INSTALLED VERTICALLY DOWN SLOPE.
3. SLOPE SURFACE SHALL BE FREE OF ROCKS, AND ORGANIC DEBRIS.
4. MATS/BLANKETS SHALL HAVE GOOD SOIL CONTACT.
5. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH
6. INSTALL SEDIMENT CONTROLS (I.E. STRAW WATTLES) IN CONJUNCTION WITH EROSION CONTROLS (I.E. ROLLED MATS, OR HYDROSEED) AS REQUIRED TO CONTROL SEDIMENT TRANSPORT.

DRAWN A.JD
DIV EROSION
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

SLOPE / STOCKPILE STABILIZATION

SCALE NTS


DATE 12/10/21

APPR


STD DWG E-5

Preliminary



01/14/2022 1:14:09 PM




LONGITUDINAL ANCHOR TRENCH
NTS



TERMINAL SLOPE AND
CHANNEL ANCHOR TRENCH
NTS



INITIAL ANCHOR TRENCH
NTS



INTERMITTENT CHECK SLOT
NTS

NOTES:

1. CHECK SLOTS TO BE CONSTRUCTED PER MANUFACTURERS RECOMMENDATIONS.
2. STAKING OR STAPLING LAYOUT PER MANUFACTURES RECOMMENDATIONS.
3. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS. MATS/BLANKETS SHALL HAVE GOOD SOIL CONTACT.
4. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS.
5. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH.

CHANNEL STABILIZATION
NTS

DRAWN LJC
DIV EROSION
REV DATE
12/1/17



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

EROSION BLANKET - CHANNEL INSTALLATION


SCALE NTS

DATE 10/01/21

APPR

STD DWG E-6

01/14/2022 1:14:09 PM



NOTES:

1. REMOVE AND LEGALLY DISPOSE OF WASTE MATERIAL WHEN IT ACCUMULATES TO $\frac{2}{3}$ OF WET STORAGE CAPACITY OF PIT.
2. CONCRETE WASHOUT AREA TO BE REPAIRED AND/OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE.
3. UPON COMPLETION OF CONSTRUCTION ACTIVITIES REQUIRING CONCRETE WASHOUT, THE WASHOUT SHALL BE REMOVED AND THE AREA RESTORED TO FINISH GRADE AND EXISTING CONDITION.
4. CONTRACTOR SHALL TAKE PRECAUTIONS SO AS TO NOT OVERFLOW PIT.

DRAWN LJC
DIV EROSION
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

CONCRETE TRUCK WASHOUT


SCALE NTS

DATE 12/1/17

APPR


STD DWG E-7

01/14/2022 1:14:09 PM



NOTES:

1. CONSTRUCTION ENTRANCE TO BE INSTALLED PRIOR TO ANY OTHER WORK ON SITE AND IS APPLICABLE AT ALL POINTS OF INGRESS AND EGRESS UNTIL SITE IS STABILIZED.
2. TIRE WASH FACILITY MAY BE REQUIRED ON SITE TO PREVENT TRACKING ONTO EXISTING ROADWAY. IF REQUIRED, CONSTRUCT TIRE WASH FACILITY PER ODOT STD DWG RD1060.
3. THE CONSTRUCTION AND USE OF THIS ENTRANCE IN NO WAY NEGATES THE CONTRACTOR'S RESPONSIBILITIES TO PREVENT TRACKING OF MATERIAL ONTO EXISTING ROADWAY.
4. MUST BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR DIRECT FLOW OF MUD/SEDIMENT ONTO STREETS. PERIODIC TOP DRESSING WITH STONE AND/OR CLEANOUT OR REPAIR SHALL BE NECESSARY.
5. ANY MATERIAL THAT STILL MAKES IT ONTO THE ROAD MUST BE SWEEPED UP IMMEDIATELY. WASHING THE STREET IS NOT PERMITTED.

DRAWN AJD	 CITY OF BEND	CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV EROSION			DATE 12/10/21
REV DATE			APPR
		GRAVEL CONSTRUCTION ENTRANCE	STD DWG E-8

Preliminary



01/14/2022 1:14:09 PM

CITY OF BEND STANDARD DRAWINGS

Landscaping (L)

01/14/2022 1:14:10 PM

PVC DRIPLINE
FEEDER MANIFOLD
(SEE DETAIL
THIS SHEET)



TYPICAL PVC DRIPLINE MANIFOLD CONNECTION

NOTES:

1. RELOCATE DRIP LINES AROUND OBSTACLES AS NEEDED

DRAWN LJC

DIV LNDSCP

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

PLANTING OR TURF BED DRIP LAYOUT


SCALE NTS

DATE 12/1/17

APPR

STD DWG L-1

01/14/2022 1:14:10 PM



DRAWN LJC
DIV LNDSCP
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701



SPRINKLER HEAD AND JOINTS

SCALE NTS

DATE 12/1/17

APPR

STD DWG L-2



NOTES:

1. COMPACTION SHALL MEET 00405.46C PER CITY OF BEND SPECIAL PROVISIONS
2. 12" MIN COVER UNDER SIDEWALKS
3. SEE STD DWGS R-10 AND R-11 FOR TRENCH BACKFILL AND ROAD RESTORATION REQUIREMENTS.

DRAWN	AJD
DIV	LNDSCP
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

IRRIGATION SLEEVE UNDER PAVING


SCALE NTS

DATE 12/10/21

APPR

STD DWG L-3

01/14/2022 1:14:10 PM



NOTES:

1. MINIMUM DEPTH OVER PVC PIPE:
10" FOR 1-1/4" OR SMALLER
12" FOR 1-1/2" TO 2" PIPE
14" FOR 2-1/2" TO 3" LATERALS
18" FOR MAINLINE PIPING AND SLEEVES
2. CLEARANCE BETWEEN PIPE:
4" FOR PIPE 2" AND SMALLER
6" FOR LARGER PIPE

3. PROVIDE A DETECTABLE TAPE OR WIRE USING A CONTINUOUS MINIMUM 14 GAUGE SINGLE STRAND LOCATOR WIRE IN TRENCH A MINIMUM 6" TO 10" BELOW FINISH GRADE. TRACING TAPE OR WIRE SHALL BE LOCATED A MINIMUM 6" ABOVE PIPING ON MAINLINE INSTALLATIONS

DRAWN LJC

DIV LNDSCP

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


IRRIGATION - TYPICAL TRENCH

SCALE NTS


DATE 12/1/17

APPR


STD DWG L-4




CROSS




ELL



45° ELL



TEE



REBAR LOOP TIE

WYE

NOTES:

1. SUPPLY LINES 3" IN DIAMETER AND LARGER SHALL RECEIVE THRUST BLOCKS
2. USE A MINIMUM 1 CU FT OF CONCRETE IN EACH THRUST BLOCK POUR

DRAWN	LJC
DIV	LNDSCP
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

IRRIGATION FITTINGS

SCALE NTS

DATE 12/1/17


APPR

STD DWG L-5

01/14/2022 1:14:10 PM

- 1 30" LINEAR LENGTH OF WIRE, COILED
- 2 WATER PROOF CONNECTION (1 OF 2)
- 3 ID TAG
- 4 VALVE BOX WITH COVER: AMETEK STANDARD OR EQUAL
- 5 FINISH GRADE/TOP OF MULCH ALLOW 2" DEPTH MIN FOR BARK IF LOCATED IN SHRUB BED

- 6 REMOTE CONTROL VALVE: AS SPECIFIED ON DRAWING
- 7 PVC SCHEDULE 40 PIPE
- 8 PVC SADDLE FEMALE THREAD
- 9 TREATED WOOD OR BRICK SUPPORT (LENGTH AS REQ'D.)
- 10 CONTROL WIRING 24 VAC
- 11 PVC MAINLINE PIPE
- 12 SCH 80 MALE ADAPTER
- 13 PVC ELECTRICAL CONDUIT SIZE AS SHOWN ON DRAWINGS
- 14 PVC SCH 40
- 15 GRAVEL BED AT BOTTOM OF BOX 6" MIN DEPTH



DRAWN LJC

DIV LNDSCP

REV DATE

1 12/10/21



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


IRRIGATION REMOTE CONTROL VALVE

SCALE NTS

DATE 12/1/17

APPR

STD DWG L-6



NOTES:

1. PROVIDE PVC BUSHINGS AS REQUIRED TO REDUCE SIZE FROM TEE.
2. QUICK COUPLER ASSEMBLY REQUIRED, SEE STD DWG L-9.
3. PROVIDE ALL THREADED PVC CONNECTIONS WITH A NON-HARDENING JOINT COMPOUND, COMPATIBLE WITH MANUFACTURERS RECOMMENDATION.

DRAWN	LJC
DIV	LNDSCP
REV	DATE
1	12/10/21



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

IRRIGATION BLOW OUT

SCALE NTS

DATE 12/1/17

APPR


STD DWG L-7



- | | |
|------------|------|
| DRAWN LJC | |
| DIV LNDSCP | |
| REV | DATE |



STD DWG L-8



DRAWN LJC

DIV LNDSCP

REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


QUICK COUPLING VALVE

SCALE NTS

DATE 12/1/17

APPR

STD DWG L-9



NOTES:

1. PROVIDE ADEQUATE SPACE FOR SERVICING THE SYSTEM
2. ALL ELECTRICAL WIRE TO BE INSTALLED IN APPROVED CONDUIT

DRAWN	LJC
DIV	LNDSCP
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

DRIP CONTROL VALVE, FILTER, AND REGULATOR


SCALE NTS

DATE 12/1/17

APPR

STD DWG L-10

01/14/2022 1:14:10 PM



NOTES:

1. ALL ELECTRICAL WIRE TO BE INSTALLED IN APPROVED CONDUIT

DRAWN LJC
DIV LNDSCP
REV DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


1" COMM. CONTROL ZONE KIT WITH BASKET FILTER

SCALE NTS

DATE 12/1/17

APPR

STD DWG L-12



NOTES:

1. PROVIDE ALL THREADED CONNECTIONS WITH A NON-HARDENING, JOINT COMPOUND, COMPATIBLE WITH MANUFACTURERS RECOMMENDATIONS

DRAWN	LJC
DIV	LNDSCP
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701

AIR RELIEF VALVE IN KIT - AR VALVE KIT

SCALE NTS

DATE 12/1/17


APPR

STD DWG L-13




1. LATERAL AND EMITTER SPACING DEPENDS ON SOIL TYPE, AND PLANT SPECIES.
2. SEE OSS - DET 6110 - PLANTING OR TURF BED DRIP LAYOUT FOR OVERALL SPECIFICATION

DRAWN LJC			CITY OF BEND		SCALE NTS
DIV LNDSCP			STANDARD DRAWING		DATE 12/1/17
REV	DATE		710 NW WALL ST., BEND, OREGON 97701		APPR
1	12/10/21		DRIP IRRIGATION MAINLINE LAYOUT		STD DWG L-14
CITY OF BEND					




NOTES:

1. USE MANUFACTURERS RECOMMENDED TOOL TO PERFORATE 1/2" POLYETHYLENE TUBING, FOR BARB CONNECTION POINTS OF ENTRY


DRAWN AJD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV LNDSCP			DATE 12/10/21
REV		POINT SOURCE DRIP EMITTER	APPR
DATE			STD DWG L-15

CITY OF BEND




NOTES:

1. IF PUTTING LANDSCAPE DRIPLINE UNDER SOIL, DO NOT BURY MORE THAN 2" BELOW GRADE AND INCLUDE AIR RELIEF VALVE (SEE DRW NO L-13 "AIR RELIEF VALVE KIT-AR VALVE KIT")

DRAWN AJD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV LNDSCP			DATE 12/10/21
REV DATE		DRIPLINE 2" BELOW GRADE POTABLE SYSTEM	APPR
	CITY OF BEND		STD DWG L-16

01/14/2022 1:14:11 PM



NOTES:

1. FURNISH FITTINGS AND PIPING NOMINALLY SIZED IDENTICAL TO NOMINAL QUICK COUPLING VALVE INLET SIZE

DRAWN LJC	
DIV LNDSCP	
REV	DATE



CITY OF BEND

CITY OF BEND

STANDARD DRAWING

710 NW WALL ST., BEND, OREGON 97701


SCALE NTS

DATE 12/1/17


APPR

STD DWG L-17

LANDSCAPE DRIPLINE FLUSH POINT POTABLE SYSTEM




PLAN




SECTION

NOTES:

1. POSITION UNITS SPACE AROUND ROOT BALL OF TREE
2. INSTALL UNITS SO TOP PF RWS (RAIN BIRD RWS-BCG) IS EVEN WITH GROUND SURFACE.
LIMIT RWS TO NO DEEPER THAN BOTTON OF ROOT BALL


DRAWN AJD			CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV LNDSCP				DATE 12/10/21
REV	DATE			APPR
				STD DWG L-18
CITY OF BEND		TREE ROOT WATERING SYSTEM DETAIL		

01/14/2022 1:14:11 PM



NOTES:

1. MINIMUM TREE WELL DIMENSIONS DICTATED BY BEND DEVELOPMENT CODE 12.2.4.1.
2. VEGETATION WITHIN THE TREE WELL SHALL HAVE DRIP SYSTEM IRRIGATION INSTALLED PER L-18.
3. TREE GRATE SHALL BE EJ 8954 PLAZA SET, OR APPROVED EQUAL.

DRAWN A.JD		CITY OF BEND STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV LNDSCP			DATE 12/10/21
REV DATE			APPR
		TREE WELL DETAIL	STD DWG L-19
	CITY OF BEND		